This is a reproduction of a library book that was digitized by Google as part of an ongoing effort to preserve the information in books and make it universally accessible.







FORESTRY SD 672 .U565



TIT TRE

THE NATIONAL FOREST MANUAL.

REGULATIONS OF THE SECRETARY OF AGRICULTURE AND INSTRUCTIONS TO FOREST OFFICERS RELATING TO AND GOVERNING TIMBER SALES, ADMINISTRATIVE USE, TIMBER SETTLEMENT, AND THE FREE USE OF TIMBER AND STONE UPON NATIONAL FOREST LANDS.

ISSUED BY THE SECRETARY OF AGRICULTURE TO TAKE EFFECT DECEMBER 1, 1911.

TIMBER SALES.
ADMINISTRATIVE USE.
TIMBER SETTLEMENT.
FREE USE.



WASHINGTON: COVERNMENT PRINTING OFFICE. 4911.

ORESTRY DEPARTMENT



SD 672 . U565 Copy 2

U. S. DEPARTMENT OF AGRICULTURE,

FOREST SERVICE.

HENRY S. GRAVES, Forester.

THE NATIONAL FOREST MANUAL.

REGULATIONS OF THE SECRETARY OF AGRICULTURE AND INSTRUCTIONS TO FOREST OFFICERS RELATING TO AND GOVERNING TIMBER SALES, ADMINISTRATIVE USE, TIMBER SETTLEMENT, AND THE FREE USE OF TIMBER AND STONE UPON NATIONAL FOREST LANDS.

ISSUED BY THE SECRETARY OF AGRICULTURE TO TAKE EFFECT DECEMBER 1, 1911.

TIMBER SALES.

ADMINISTRATIVE USE.

TIMBER SETTLEMENT.

FREE USE.



WASHINGTON: GOVERNMENT PRINTING OFFICE, 1911. DEPARTMENT

Digitized by Google

The Secretary * * * may make such rules and regulations * * * as will insure the objects of such reservations, namely, to regulate their occupancy and use and to preserve the forests thereon from destruction; and any violation of the provisions of this act or such rules and regulations shall be punished [by \$500 fine or 12 months' imprisonment, or both] as is provided for in the act of June 4, 1888, amending section 5388 of the Revised Statutes of the United States. (Act of June 4, 1897, 30 Stat., 11.)

CONTENTS.

	* mg0.
Regulations	7
Timber sales	7
Appraisal of timber	
Limitation of annual cut	
Maximum and minimum prices	7
Authority to make sales. Deposits.	
Deposits.	
Payments and refunds	
Installment payments	
Modification of contracts	
Advance cutting	
Private sale	
Private sale. Prevention of monopoly; award of sales to trespassers	
Exportation of timber.	
Conditions of sale	
Time limits.	
Bonds	
Appeals	10
Use of steam engines of locomotives.	10
Administrative use of timber	10
Timber settlement	10
Free use of timber and stone.	1
By whom granted	1
To whom granted	
To whom refused	10
Amount	11
Restrictions on free use of saw timber	1:
Free use without permit	1:
Free-use areas	11
Sale of material prohibited	. 1:
Special conditions in Alaska	1:
Special conditions in Alaska	13
Timber sales.	1
Limitation of annual cut	1
Maximum and minimum stumpage prices.	1
Classification of sales.	
Class A — Rangore' soles	i
Class A—Rangers' sales Class B—Supervisors' sales not exceeding \$100	ī
Class C. Supervisors' advortised sales	1
Class C—Supervisors' advertised sales. Class D—District forester's and Forester's sales.	i
Advertisement	20
Advertisement. Bids and awards.	
Contracts.	
Bonds.	
Advance cutting	
Private sale	. 2
Sale of material seized	. 2
Payments, deposits, refunds, and transfers	. 2
Modification of contracts	. 3
Cancellation of contracts	. 3
Special uses connected with sales	. 3
Period for removal.	. 3
Period for removal. Examination of timber applied for and preparation of the application.	. 3
The second of th	

CONTENTS.

Procedure and instructions—Continued.	
Timber sales—Continued.	P
Administration of sales—general	-
Marking	
Brush disposal	
Scaling	
Sale of miscellaneous forest products	
Appeals	
Records and reports	
Administrative use of timber	
Timber settlement	
Free use of timber and stone	
Timber-sale and free-use forms.	
Bid for advertised timber	
Timber-sale agreement	
Bond	
Memorandum of corporate officer's authority to sign instrument	
Free-use permit.	
Index	

United States Department of Agriculture, Office of the Secretary, Washington, D. C.

By virtue of the authority vested in the Secretary of Agriculture by the act of Congress of February 1, 1905 (33 Stat., 628), amendatory of the act of Congress of June 4, 1897 (30 Stat., 11), I, James Wilson, Secretary of Agriculture, do make and publish the following regulations for timber sales, administrative use, timber settlement, and the free use of timber and stone upon National Forest lands, the same to supersede all previous regulations for like purposes and to be in force and effect from the 1st day of December, 1911, and to constitute a part of the Use Book.

In testimony whereof I have hereunto set my hand and official seal, at Washington, D. C., this 31st day of October, 1911.

JAMES WILSON, Secretary of Agriculture.

5

THE NATIONAL FOREST MANUAL

REGULATIONS.

TIMBER SALES.


Reg. S-1. No timber shall be designated for cutting, by stamping or otherwise, until the officer approving the sale is Appraisal of timsatisfied that the cutting will preserve the living and growing timber, promote the younger growth, and be compatible with the utilization of the Forest. Upon application for the purchase of any timber or in any cases where timber is to be advertised in advance of application, such timber shall be examined and appraised, and the area from which the timber is to be cut shall be described by legal subdivisions or otherwise. The officer making the field examination shall report the quantity and value of the various kinds of timber involved, and shall base his appraisal upon the character of the timber, the cost of logging, transportation, and manufacture, and the sale value of the manufactured products at practicable markets.

Reg. S-2. The Secretary of Agriculture will prescribe each year, upon data and information furnished by the Forester, the maximum amount of dead, matured, and large-growth timber that may be cut on each

National Forest.

The Secretary of Agriculture will prescribe each year, upon data and information furnished by the Forester, the Maximum and minimum stumpage prices at which the timber on each National Forest or designated portion thereof shall be appraised. Appraisals higher than the established maximum and lower than the established minimum shall be made by Forest officers, in so far as the local conditions in each specific sale warrant. No appraisals at less than the established minimum or more than the established maximum shall be approved by any Forest officer authorized to sell timber until the approval of such appraisals by the Secretary of Agriculture has been secured.

Reg. S-3. The Forester is authorized to make timber sales for any amount on any National Forest, provided the limit Authority to make fixed by the Secretary for any Forest is not exceeded by the year's cut, under sales and free use on such Forest; and to delegate this authority for any specified amounts to the district foresters, but in no instance to exceed 20,000,000 feet board measure. The district forester may in turn delegate authority



SD 672 . U565 Copy2

U. S. DEPARTMENT OF AGRICULTURE,

FOREST SERVICE.

HENRY S. GRAVES, Forester.

THE NATIONAL FOREST MANUAL.

REGULATIONS OF THE SECRETARY OF AGRICULTURE AND INSTRUCTIONS TO FOREST OFFICERS RELATING TO AND GOVERNING TIMBER SALES, ADMINISTRATIVE USE, TIMBER SETTLEMENT, AND THE FREE USE OF TIMBER AND STONE UPON NATIONAL FOREST LANDS.

ISSUED BY THE
SECRETARY OF AGRICULTURE
TO TAKE EFFECT
DECEMBER 1, 1911.

TIMBER SALES.
ADMINISTRATIVE USE.
TIMBER SETTLEMENT.
FREE USE.



WASHINGTON: GOVERNMENT PRINTING OFFICE, 1911.

The Secretary * * * may make such rules and regulations * * * as will insure the objects of such reservations, namely, to regulate their occupancy and use and to preserve the forests thereon from destruction; and any violation of the provisions of this act or such rules and regulations shall be punished [by \$500 fine or 12 months' imprisonment, or both] as is provided for in the act of June 4, 1888, amending section 5388 of the Revised Statutes of the United States. (Act of June 4, 1897, 30 Stat., 11.)

CONTENTS.

	Page
Regulations	
Timber sales	
Appraisal of timber	
Limitation of annual cut	
Maximum and minimum prices	
Authority to make sales	
Deposits	. :
Deposits Payments and refunds	
Installment payments	
Modification of contracts.	
Advance cutting	
Privata sala	
Private sale. Prevention of monopoly; award of sales to trespassers	
Exportation of timber.	
Conditions of sale.	
Time limits	
Bonds.	
Appeals	. 1
Use of steam engines or locomotives	. 1
Administrative use of timber.	. 1
Timber settlement.	. 1
Free use of timber and stone.	. 1
By whom granted	. 1
To whom granted	. 1
To whom refused	. 1
Amount	. 1
Restrictions on free use of saw timber	. 1
Free use without permit.	. 1
Free-use areas	. 1
Sale of material prohibited	. 1
Special conditions in Alaska	. 1
Special conditions in Alaska	. 1
Timber sales.	. 1
Limitation of annual cut.	. 1
Maximum and minimum stumpage prices	. 1
Classification of sales	. 1
Class A—Rangers' sales	. 1
Class A—Rangers' sales Class B—Supervisors' sales not exceeding \$100.	. ī
Class C—Supervisors' advertised sales. Class D—District forester's and Forester's sales.	. 1
Class D.—District forester's and Forester's sales	. î
Advertisement	$\tilde{2}$
Bids and awards.	$\overline{2}$
Contracts	
Bonds.	
Advance cutting.	
Private sale	
Sale of material seized	
Payments, deposits, refunds, and transfers	. 2
Modification of contracts	. 3
Cancellation of contracts	. 3
Special uses connected with sales	. 3
Period for removal Examination of timber applied for and preparation of the application	. 3
Examination of timber applied for and preparation of the application	. 3

CONTENTS.

Procedure and instructions—Continued.	
Timber sales—Continued.	Ŧ
Administration of sales—general	
Marking	
Brush disposal	
Scaling	
Sale of miscellaneous forest products.	
Appeals	
Records and reports.	
Administrative use of timber.	
Timber settlement	
Free use of timber and stone.	
Timber-sale and free-use forms.	
Bid for advertised timber.	
Timber-sale agreement.	
Bond	
Memorandum of corporate officer's authority to sign instrument	
Free-use permit.	
Index	

United States Department of Agriculture, Office of the Secretary, Washington, D. C.

By virtue of the authority vested in the Secretary of Agriculture by the act of Congress of February 1, 1905 (33 Stat., 628), amendatory of the act of Congress of June 4, 1897 (30 Stat., 11), I, James Wilson, Secretary of Agriculture, do make and publish the following regulations for timber sales, administrative use, timber settlement, and the free use of timber and stone upon National Forest lands, the same to supersede all previous regulations for like purposes and to be in force and effect from the 1st day of December, 1911, and to constitute a part of the Use Book.

In testimony whereof I have hereunto set my hand and official seal, at Washington, D. C., this 31st day of October, 1911.

James Wilson, Secretary of Agriculture.

5

THE NATIONAL FOREST MANUAL.

REGULATIONS.

TIMBER SALES.

Appraisal of timber.

Appraisal of timber.

Appraisal of timber.

Appraisal of timber.

Ber.

Appraisal of timber.

Satisfied that the cutting will preserve the living and growing timber, promote the younger growth, and be compatible with the utilization of the Forest. Upon application for the purchase of any timber or in any cases where timber is to be advertised in advance of application, such timber shall be examined and appraised, and the area from which the timber is to be cut shall be described by legal subdivisions or otherwise. The officer making the field examination shall report the quantity and value of the various kinds of timber involved, and shall base his appraisal upon the character of the timber, the cost of logging, transportation, and manufacture, and the sale value of the manufactured products at practicable markets.

Reg. S-2. The Secretary of Agriculture will prescribe each year, upon data and information furnished by the Forester, the maximum amount of dead, matured, and large-growth timber that may be cut on each

National Forest.

The Secretary of Agriculture will prescribe each year, upon data and information furnished by the Forester, the maximum and minimum stumpage prices at which the timber on each National Forest or designated portion thereof shall be appraised. Appraisals higher than the established maximum and lower than the established minimum shall be made by Forest officers, in so far as the local conditions in each specific sale warrant. No appraisals at less than the established minimum or more than the established maximum shall be approved by any Forest officer authorized to sell timber until the approval of such appraisals by the Secretary of Agriculture has been secured.

Reg. S-3. The Forester is authorized to make timber sales for any amount on any National Forest, provided the limit fixed by the Secretary for any Forest is not exceeded by the year's cut, under sales and free use on such Forest; and to delegate this authority for any specified amounts to the district foresters, but in no instance to exceed 20,000,000 feet board measure. The district forester may in turn delegate authority

to supervisors to make sales for specified amounts, which in no instance shall exceed 2,000,000 feet board measure. All supervisors may, without special authorization, make sales of timber and cordwood in amounts not exceeding \$100 in value in any one sale. The supervisor may authorize subordinate Forest officers to make sales of timber and cordwood in amounts not exceeding \$50 in value in any one sale.

Reg. S-4. The supervisor may, in his discretion, require that a deposit be made with the proper United States depository before any timber applied for is examined. In every case where a supervisor decides to recommend a sale of timber for which advertisement is required by law, he will notify the applicant to forward to the proper United States depository such part of the purchase price as will be sufficient to cover the cost of advertising; such deposit to be applied to the purchase price in case the sale is made to the depositor; to be refunded in case the sale is made to some one other than the depositor; to be retained in the discretion of the officer approving the sale, if, through fault of the depositor, no sale of the timber is made.

Reg. S-5. No timber shall be cut under any timber sale contract until it has been paid for. Refunds may, in the discretion of the Forester or district forester, be made to depositors of such sums deposited by them to secure the purchase price of forest products as may be found to be in excess of the amounts actually due the United States. Refunds or payments may also be made to the rightful claimants of such sums as may be found to have been erroneously collected for timber

National Forest.

Reg. S-6. In any sale the timber may be paid for in one or more number payments, as agreed. In sales of \$100 or less the partial payments must not exceed three.

or other forest products sold from lands within, but not a part of, a

Reg. S-7. Modifications of contracts for the sale of timber will not be allowed except in those cases where the full percontracts.

Modification of formance of the contract by the purchaser is rendered inequitable and unjust by some act of the United States, or except where the modification is sought in respect to the unexecuted portion of the contract and such modification would not be prejudicial to the interests of the United States. Modifications, where proper, within the meaning of this regulation, may be made by

Reg. S-8. No timber will be sold, other than in amounts not exceeding \$100 stumpage value, in advance of advertisement, except in cases of unusual emergency. All applications for emergency sales of timber will be submitted to the Secretary of Agriculture for approval, with a statement setting forth the reasons for the emergency. When application is made for timber to meet an unusual emergency the Forest officer authorized to make the sale will, when practicable and proper, include in the advertisement of such timber a sufficient quantity of other timber in the same locality and of the same class to satisfy such other bids as may be reasonably anticipated. After approval by the Secretary, the Forest officer may, in sales not exceeding the amount which such officer is authorized to approve, permit the cutting and removal of

timber in advance of the award, when the applicant has made a deposit covering the value of the timber to be cut and removed, and has agreed to pay for all timber actually cut under the privilege of advance cutting at the rate of the highest price bid for the whole amount of timber advertised, or, if no bids are received, at the rate named in the advertisement. When necessary to protect the Government against loss a bond will be required.

Reg. 8-9. After any timber has been advertised and no satisfactory bid has been received, or if the bidder fails to complete the purchase, Forest officers may, within their authorization, dispose of it at private sale, in quantities to suit purchasers, without further advertisement, at prices not lower than

those named in the advertisement.

Timber may also be disposed of at private sale without advertisement where the stumpage value of the timber does not exceed \$100.

Reg. S-10. In awarding advertised timber of a value exceeding \$5,000, allotments at the highest price offered may nopoly. Award of be made to several bidders to prevent monopoly. Bids submitted by parties who have trespassed upon any National Forest will not be considered unless full settlement has been previously made for such trespass.

Reg. S-11. Timber cut from any National Forest may be exported from the State or Territory in which the National Forest is situated, except that from the Black Hills

National Forest in South Dakota only dead and insect-infested timber may be exported from the State, and this only until the date upon which the Forester shall certify that the ravages of the destructive insects in said Forest are practically checked, but in no case after such date or dates as Congress has specified or shall hereafter specify. Timber cut from any National Forest in Alaska may be exported therefrom and sold anywhere, upon certification by the supervisor that the timber has been purchased and cut from a National Forest in Alaska.

Reg. S-12. No trees on National Forest lands, or from any unpatented claim within National Forests, shall be cut, or otherwise killed, injured, or destroyed, except under permit or where allowed by law in the development of the

claim.

No trees on any unpatented claim within National Forests shall be cut under permit, until the written consent of the claimant has been filed with the Forest supervisor, except in emergencies arising from insect infestation.

No live trees shall be cut under any contract until marked or other-

wise designated by a Forest officer.

No timber cut under any contract shall be removed from the place selected for scaling, measuring, or counting until it has been scaled, measured, or counted and stamped by a Forest officer.

No person except a Forest officer shall stamp any timber belonging to the United States upon a National Forest with the regulation

marking ax or with any instrument having a similar design.

All saw timber will be scaled by Scribner Decimal Clog rule, as used by the Forest Service.

Reg. S-13. The period allowed for the removal of timber, which in no instance shall exceed five years, except in special cases upon specific approval by the Secretary, will be fixed in the agreement, and in sales in which a period of two or more years is allowed for the removal of the timber, the minimum amount to be removed each year must be specified, except in unusual cases. The Secretary may, in his discretion, when circumstances warrant, extend the time beyond a period of five years; but such extension will be granted only to prevent hardship in cases where the failure to remove the timber within the five-year period is due to circumstances over which the purchaser had no control.

Reg. S-14. The officer approving any timber-sale contract may require the purchaser to furnish a bond for the satis-

factory completion of the contract.

Reg. S-15. The disapproval of an application for the purchase of timber or for the modification of an existing contract by the officer authorized to approve such application shall be considered final unless written notice of appeal to the next superior officer, district forester, Forester, or Secretary, as the case may be, is filed with the officer disapproving such application within 30 days from the receipt of his decision. All appeals arising from the enforcement or execution of the provisions of a timber-sale contract shall be made in the first instance to the Forest supervisor. His decision thereon shall be considered final unless written notice of appeal to the district forester is filed with the supervisor within 15 days from the receipt of his decision. Appeals from the decisions of the district forester to the Forester or from the decisions of the Forester to the Secretary may be made by filing written notice with the officer from whose decision appeal is taken within 15 days from the receipt of such decision.

Reg. S-16. The use of steam engines or steam locomotives in operations on National Forest lands under any timber-sale contract or under any permit is prohibited unless they are equipped with such spark-arresters as shall be approved by the Forest supervisor, or unless oil is used exclusively

for fuel.

ADMINISTRATIVE USE OF TIMBER.

Reg. S-17. The Forester, and the district foresters within the amount which they are authorized to sell, may remove and sell or dispose of, under free-use permit or otherwise, as shall be most advantageous to the United States, any timber upon the National Forests when such removal is actually necessary to protect the Forest from ravages or destruction, or when the use or removal of timber is necessary in the construction of roads, trails, cabins, and other improvements on the National Forests or in experiments conducted by the Forest Service. The authority conferred by this regulation may be delegated by district foresters to Forest supervisors.

TIMBER SETTLEMENT.

Reg. S-18. When timber on National Forest land is cut, damaged, killed, or destroyed in connection with the enjoyment of a right of way or other special use it shall not be necessary to advertise it for

sale, but payment therefor may be required at such rate or rates as may be fixed by the officer authorized, under the timber-sale regulations, to sell the amount of timber involved, but in no case for less than the minimum or for more than the maximum price established by the Secretary of Agriculture, unless the authority of the Secretary is secured. When, however, a right of way or other special use is granted within a National Forest in Alaska, the supervisor may; without charge, allow the cutting of timber when this is necessary for the proper enjoyment of the special use.

FREE USE OF TIMBER AND STONE.

Reg. S-19. The Secretary of Agriculture will determine for each fiscal year, upon data to be furnished by the Forester, the maximum amount of timber to be cut under free use on each Forest, which amount shall form a part of the total maximum cut for the Forest. The Forester may grant free-use permits for timber not exceeding \$500 in value, and may delegate this authority to subordinate officers. Permits for timber in excess of \$100 in value, except in cases of unusual emergency, will be granted only for public purposes. Supervisors, unless otherwise authorized, may not grant permits for material exceeding \$100 in value. All Forest officers whom the supervisor may designate are authorized to grant free-use permits up to \$20 in value. The Forester is also authorized to grant free use of stone and to delegate this authority to subordinate officers. All applications for free use of timber of value above \$500 will be submitted to the Secretary of Agriculture for approval.

Reg. S-20. Free-use permits may be granted to bona fide settlers, miners, residents, and prospectors for minerals, who may not reasonably be required to purchase, and who have not on their own lands, or claims, or on lands controlled by them, a sufficient or practically accessible supply of material suitable for the purposes named in the law. They may also be granted to school and road districts, churches, or noncommercial cooperative organizations of settlers desiring to construct roads, ditches, reservoirs, or other similar improvements for mutual or public benefit. Free use may be granted to other branches of the Federal Govern-Free use may be granted for consumption outside the State in which the National Forest is located, except from the Black Hills National Forest in South Dakota, on which Forest the free use of dead and insect-infested timber only may, until the date upon which the Forester shall certify that the insect ravages are practically checked, but in no case after such date or dates as Congress has specified, or shall hereafter specify, be granted for consumption outside the State.

Reg. S-21. Trespassers will not be granted free use until full settlement has been made by them. Free use of material to be used in any business will be refused, as, for example, to sawmill proprietors, owners of large establishments or commercial enterprises, companies, and corporations.

Reg. S-22. No applicant will be given more than two free-use

Reg. S-22. No applicant will be given more than two free-use permits in one year, nor may the aggregate amount of material granted in the two permits exceed \$20 in value, except in cases of great and unusual need, or in the case of

school and road districts, churches, and noncommercial cooperative organizations of settlers, when the supervisor may, in his discretion, extend the amount to any value not exceeding \$100, or the value named in his authorization from the district forester. If the permittee fails to remove timber within the time allowed, the Forest officer may grant the timber to another applicant. The time allowed in permits may be extended by the officer issuing them in cases of unusual emergency.

Reg. S-23. Green saw timber will not be granted to any appli-Restrictions on cant who does not do his own logging, unless he is physically incapacitated. Exceptions, however, may be made in unusual cases in the judgment of the All free-use material may be sawed and all except green timber may be cut for the permittee by an agent, but the work so done must not be paid for by a share of the material. On Forests where a limited supply or other conditions justify it, the free use of all green saw timber or both green and dead saw timber may be refused.

Reg. S-24. Necessary cutting of timber in surveying for lawful Free use without projects may be done without permit. Unnecessary cutting is prohibited.

No free-use material, except the small quantities actually needed

by transients, will be taken without a written permit.

Reg. S-25. Supervisors may, with the approval of the district foresters, establish temporary free-use areas from which bona fide settlers, miners, residents, and prospectors for minerals may take, in quantities specified in Regulation S-22, dead fuel timber, dead fencing material, either or both in the discretion of the district forester, without the material being scaled or measured by a Forest officer. While permits are required in all cases, it is not necessary that they be obtained in advance when the material is secured from a designated free-use area. In every instance where a permit has not been obtained in advance, the person taking material from a temporary free-use area shall promptly thereafter notify the Forest officer in charge of the district in which such area is located of the date of removal, and of the amount, value, and class of material so taken. Upon receipt of such notification the Forest officer will issue the necessary permit.

Reg. S-26. Timber or other forest products received

under a free-use permit shall not be sold.

Reg. S-27. Settlers, farmers, prospectors, fishermen, or similar persons residing within or adjacent to National Forests Special conditions in Alaska. in Alaska may take, without permit and free of charge, green or dry timber from the Forests, and driftwood, afloat or on the beaches, for their own personal use, but not for sale; provided, that the amount of material so taken shall not in any one year exceed 20,000 feet board measure, or 25 cords of wood; and provided further, that the persons enjoying this privilege will, on demand, forward to the supervisor a statement of the quantity of material so taken and a description of the location from which it was removed.

PROCEDURE AND INSTRUCTIONS IN TIMBER SALES, ADMINIS-TRATIVE USE, TIMBER SETTLEMENT, AND FREE USE.

United States Department of Agriculture, FOREST SERVICE. Washington, D. C., October 31, 1911.

The following procedure and instructions are hereby established and issued, to take effect December 1, 1911, governing the enforcement of the regulations of the Secretary of Agriculture relating to timber sales, administrative use, timber settlement, and the free use of timber and stone upon the National Forests.

H. S. GRAVES. Forester.

Approved. JAMES WILSON, Secretary of Agriculture.

TIMBER SALES.

LIMITATION OF ANNUAL CUT.

The supervisor of each Forest will recommend to the district forester annually on April 1 the maximum amount of timber which should be cut from the Forest during the ensuing fiscal year, which shall include a specified amount which may not be exceeded under

On Forests for which working plans have been prepared, the working plan will provide a basis for determining what the maximum annual cut should be. Where no working plan exists, the maximum cut will be based upon the most accurate estimate of the stand of merchantable timber, assuming a

rotation based on the best available growth data.

On Forests or working units where the demand is very great as compared with the supply, much more care must be exercised in determining the limitation than where the demand is comparatively light and there is no danger of overcutting. When market conditions are such that it is possible to utilize small timber from needed thinnings or inferior material suitable for minor uses which would otherwise go to waste, the limitation may be higher than if it is possible to market only large material suitable for saw timber.

Special attention must be given to compartments containing protection Forests. Where such areas occur the recommended cut should be greatly reduced or the areas eliminated in the calculations.

On two or more adjacent Forests where conditions are very similar and the general plan of management is the same, it may be advisable, where the timber should be cut and it is possible to obtain purchasers, to treat the maximum cut for a group of Forests as a whole. To do this special authority must be obtained from the Secretary.

MAXIMUM AND MINIMUM STUMPAGE PRICES.

The supervisor of each Forest will recommend annually to the district forester on April 1 the maximum and minimum stumpage rates which should be fixed for the Forest for the ensuing fiscal year.

Maximum and minimum stumpage prices will be recommended, with such classification as to species, accessibility, and grade of material as may be necessary to cover adequately all conditions existing on the Forest. Flat rates applicable to two or more species should be recommended wherever advisable. All rates should be based upon the thousand feet, board measure, and will be applied to other units of quantity in ratios established by these instructions or specifically approved by the Forester. The rates recommended should be based as far as practicable upon those obtained in current sales, with reasonable latitude to make them applicable to the more or less accessible and desirable timber.

Upon receipt and review of the supervisor's recommendations on maximum and minimum stumpage rates and limitation of cut, a letter in triplicate will be prepared in the district office annually by April 15. The original

and one carbon will be forwarded for the signature of the Forester and the approval of the Secretary of Agriculture, limiting the annual cut and establishing maximum and minimum rates on the Forest for the following fiscal year. After approval the original will be retained by the Forester and the carbon returned to the district forester, who will fill in the signature on the third copy and send it to the supervisor.

CLASSIFICATION OF SALES.

Sales are divided into the following classes:

Class A: Ranger's sales, no one sale exceeding \$50 in value.

Class B: Supervisor's sales, no one sale exceeding \$100 in value.

Class C: Supervisor's sales for such amounts exceeding \$100 in value as the supervisor is authorized to advertise and sell, in no case over 2,000,000 feet board measure.

Class D: District forester's and Forester's sales exceeding the

amounts which supervisors are authorized to sell.

Unadvertised sales: Sales not exceeding \$100 in amount may be made for not less than the appraised value of the timber and need not be advertised.

Advertised sales: Sales exceeding \$100 in amount must be advertised.

Private sales: Timber which has been advertised but for which no satisfactory bid has been received may be sold at any time at not less than the highest bid received and in no case at less than the minimum price specified in the advertisement.

CLASS A: RANGER'S SALES.

If an examination of the timber as outlined on page 36 shows that it should be sold, the Forest officer will designate the timber to be cut and fix the terms of sale.

The contract will be prepared in triplicate and executed and approved in duplicate. The purchaser should send the required payment to the proper United States depository with a letter of transmittal given him by the Forest officer, who will fill out two copies, mark one "Duplicate" and forward it to the supervisor. Remittances should be made by postal money order, express order, or New York draft. Currency may be sent at owner's risk. Postage stamps, foreign money, uncertified checks, or defaced coin will not be accepted. The Forest officer, upon assurance that the required payment has been forwarded to the proper United States depository, will approve both copies of the contract and permit cutting and removal. He will forward the original to the supervisor, give the duplicate to the purchaser, and keep the triplicate for his files.

Extension of cutting period, modification of the contract, or postponement of brush piling may be approved by the officer approving the sale, under the limitations imposed by regulation S-7. Copies of all such modi-

fications, including extensions, shall be sent to the supervisor.

Copies of the map and Forest description will be sent to the supervisor with the other papers. In sales of dead timber only, however, such copies need not be furnished unless specifically required by the supervisor.

Upon receipt from the ranger of the original of the contract and duplicate letter of transmittal in the supervisor's office they will be examined as to their correctness and to determine if consistent with approved and existing

rates and policy. A white timber sale record card (Form 615) will be filled out and filed alphabetically. The duplicate letter of transmittal will be placed in a reminder file, which will be examined weekly and the ranger notified of cases in which payments are two weeks late. Upon receipt from the district fiscal agent of the original letter of transmittal with the proper notation of receipt, the amount paid will be checked against the amount due, as shown by the letter of transmittal, and the amount paid and date of receipt entered on the timber sale record card. The original will then be forwarded to the payee and the duplicate, with a notation of payment received, to the ranger. Should the notification of receipt reach the supervisor before the letter of transmittal from the ranger, the data will be entered on a timber sale record card and completed upon receipt of the letter of transmittal and contract from the ranger.

Unless required by the supervisor, cutting reports (Form 820) need not be submitted until the sale is ready for closing. They will be compared with the card record as directed

under "Records and reports," page 59.

The ranger will submit a cutting report (Form 820) in duplicate with his recommendations. If approved by the supervisor the duplicate copy will be stamped "This case is closed" and returned to the ranger, who will transfer the

folder to the closed files. The supervisor will retain the original and will transfer the folder and the card (Form 615) to his closed cases.

CLASS B: SUPERVISOR'S SALES NOT EXCEEDING \$100 IN VALUE.

Application may be made through any Forest officer, but the supervisor must approve the contract. If the latter decides that a sale should be made, after an examination in accordance with the instructions on page 36, the applicant should forward to the United States depository the payment required, and receive from the supervisor an approved copy of his contract. Procedure in other respects follows that outlined under class A sales.

Where no living timber is involved, maps or Forest descriptions need not be prepared unless they are required by the Maps and Forest description.

Maps and Forest description.

Forest officer making the examination.

Since the law definitely limits the amount of timber which can be sold in an individual sale without advertisement to a way not exceed value of not more than \$100, great care will be taken. in making class B sales, that the value does not exceed It is safer to make the sale a little under the \$100 limit to allow for possible excess cutting. If the value of the timber cut exceeds \$100 it will be necessary to make a new sale of the amount cut in excess, but where the amount of a sale together with a small overcut does not exceed \$100 the overcut should be accounted for as an excess cutting on the original contract.

Repeated sales of unadvertised timber to the same Repeated sales. purchaser, in order to avoid advertising, are not per-

mitted.

CLASS C: SUPERVISOR'S ADVERTISED SALES.

The amount of timber which can be advertised is limited to the amount named in the supervisor's letter of authority, Application. whether the timber is advertised under a general notice or in response to an application. This authority is given only to the person named in the letter, and is not incident to the office.

Upon receipt of an informal application to purchase timber the Forest supervisor will determine, in accordance with the procedure outlined under "Examination of timber applied for," on page 36,

whether the sale can be made.

The formal application will be prepared in quadruplicate. copies will be transmitted to the applicant, the original of which should be executed and returned to the supervisor. A copy will be forwarded to the ranger.

Upon receipt of the formal application or upon receipt of the report in general notice sales, the case will be recorded on a salmoncolored timber-sale record card (Form 615) which will be filed under

timber sales alphabetically.

The notice of sale will be prepared in triplicate by the supervisor as soon as the application is approved and the adver-Notice of sale. tising deposit of \$50 has been made. The signed original will be sent to the publisher; the first carbon, on which the name of the newspaper is entered, will be sent to the district forester, and the second carbon filed.

As soon as the first publication has appeared, it should be compared with the file copy for mistakes. One copy of Report of adver- Form 935, with published notice attached, must be sent to the district forester, and a second copy filed by the last date for receiving bids as a reminder of the expiration of the advertisement.

The form of notice of sale and further instructions are given under

"Advertisement," page 20.

The original applicant and other prospective bidders will be notified as soon as publication has begun, instructed to Bids and awards. forward bids within the period specified in the notice of sale, and furnished with Form 941 and salmon-colored bid envelopes. (See p. 23, under "Bids and awards.")

The supervisor should notify the successful bidder that the sale has been awarded to him and that the final agreement, and bond if

required, will be sent to him within a specified time.

A copy of all bids submitted shall be marked "For the information.

of the district forester," and forwarded to the district office.

Further instructions are given under "Bids and awards," page 23. The final contract will be prepared on Form 202 in quadruplicate and executed and approved in duplicate. The approved original is for the supervisor's files, the duplicate for the purchaser, the third copy will be forwarded immediately after approval to the district forester, and the fourth copy, showing the dates and signatures of execution and approval, should be sent to the officer in charge of the sale.

Further instructions are given under "Contracts," page 23.

If a bond is required the supervisor will prepare it in duplicate on Form 377, send the original to the purchaser for exe-Bonds. cution with the contract and the duplicate to the district forester properly filled in immediately after the execution and approval of the original. The original will be approved by the supervisor and filed with his record of the case.

Further instructions are given under "Bonds," page 24.

If advance cutting is allowed by the Secretary, the application will be prepared in quadruplicate and executed in dupli-Advance cutting. cate. The original agreement after approval by the supervisor is for the supervisor's files, the duplicate for the purchaser, and the third and fourth copies with the dates of execution and approval written in for the district forester and the officer in charge of the sale. Instructions governing advance cutting are given on page 25.

The letter of transmittal (Form 861) will be made out in duplicate by Forest officers and the original sent to the pur-Letter of trans- chaser to be forwarded with each deposit to the proper United States depository; the duplicate will be filed in the supervisor's office in a waiting file and handled thereafter as

in class A sales.

Copies of the map, estimate, report, application, notice of sale, Form 935, contract, bond, and important modifica-District forester's tions will be submitted to the district forester as they are prepared, except the contract and bond, which will be submitted after execution and approval.

Class C sales will be closed in the same manner as

Closing. class A sales.

The application and report in advertised sales will be examined for the purpose of ascertaining whether they are in Procedure, dis- accordance with the preceding instructions and with instructions to the supervisor as to price, amount, period, and other conditions. Special care is necessary to see that cutting will be done in accordance with the preliminary or final working plan, and that the plan for marking agrees with the policy adopted for the Forest and type.

The carbon of the notice of sale will be checked, with particular attention to the period allowed for submitting bids, the location of

the cutting areas, the estimate, price, and deposits required.

The published notice of sale (Form 935) will be checked with the carbons previously received from the supervisor, and filed as a

reminder against the receipt of the contract and bond.

If advance cutting has been allowed, the copy of the application will be reviewed. When the papers have been reviewed, they will be returned to the supervisor, with instructions or comments if

necessary. No record will be kept in the district office.

Supervisors who have shown their ability to handle class C sales properly may, in the discretion of the district forester, be authorized to discontinue sending papers to the district office, except when necessary for examination by district assistants to the solicitor of authority of officers of incorporated companies to execute the contract for the company.

CLASS D: DISTRICT FORESTER'S AND FORESTER'S SALES.

The steps are the same as in class C sales until the supervisor has received the formal application signed by the appli-District forester's sales, application. cant. If the supervisor decides to recommend the sale, he will notify the applicant to forward \$50 to the proper United States depository to cover the cost of advertising, and will send the application to the district forester with the report, estimate, and map. If the supervisor recommends the approval of the application without modification, he will initial in the lower lefthand corner of the first page. If he wishes to recommend any modification of the application or to give a more detailed explanation of any features of the examination or application, he will do so in a letter sent with the other papers.

Where advisable, a sample contract, unexecuted, containing all of the provisions of the proposed sale, may be submitted to the district forester in lieu of a formal Sample contract. When, however, the privilege of advance cutting is application. desired the applicant will in every instance be required to sign a formal application before his application for advance cutting will be

considered.

A blue timber-sale record card (Form 615) will be Card record. filled out by the supervisor and filed as in class A sales. The application or sample contract will be examined by the district forester as under class C sales, and if approved, a timber-sale record card (Form 615) will be filled out and filed.

The supervisor will be notified immediately of any necessary modifications in the application, and will obtain the Changes in appliconsent of the applicant to such modifications before proceeding with the notice of sale.

Digitized by GOOGLE

After approval of the application or sample contract and receipt of deposit to cover advertising, a notice of sale will be prepared in the district office, with two carbons, the original signed by the district forester, and with one carbon sent to the supervisor, who will have it published in accordance with the instructions under "Advertisement," page 20.

As soon as the advertisement begins, the supervisor will check the

published notice of sale with the file copy for mistakes, and forward Form 935 to the district forester. Report of adver-The published notice of sale (Form 935) will be reviewed by the district forester and filed as a promise card to check

the expiration of the advertisement.

The supervisor will notify the original applicant and other prospective bidders as soon as advertisement is begun, Bids and awards. instructing them to forward their bids within the period specified in the notice of sale. He will furnish them with copies of Form 941 and blue bid envelopes.

After the bids are opened, the district forester will immediately notify the supervisor of the names of bidders, the amount of each

bid, and the award. See "Bids and awards," page 23.

A contract, Form 202, will then be prepared by the district forester One copy will be filed and the with four carbons. original and three carbons sent to the supervisor, who will have the original and one carbon executed by the purchaser and return them to the district office. The third copy will be retained in the supervisor's files, and the fourth sent to the officer in charge of the sale. The contract will be submitted to the district assistant to the solicitor for examination. After the district forester has approved both copies, the duplicate will be forwarded to the purchaser through the supervisor and the original filed in the safe.

When the approved duplicate of the contract is received by the supervisor, he will enter the signature and dates of execution and approval on his copy, and notify the officer in charge of the sale in

order that the latter may take the same action.

The bond, if one is necessary, will be prepared in duplicate and the original sent to the purchaser for execution through The bond. the supervisor. The executed and approved original will be submitted to the district assistant to the solicitor for examination and will be retained in the district office. The duplicate, with dates and signatures filled in, will be filed with the supervisor.

Application for advance cutting will be prepared by the supervisor in quadruplicate, and executed and forwarded in duplicate to the district forester. The district forester will review the application, and approve it if satisfactory and such action appears advisable, after obtaining authority from the Secretary. The original will be retained in the district office and the duplicate returned to the supervisor. The supervisor will make the necessary entries on the remaining copies, forward the duplicate to the purchaser, retain the third copy, and send the fourth to the officer in charge of the sale.

If the application is disapproved, the supervisor will be directed to

inform the purchaser of the reasons for such action.

In the discretion of the district forester, supervisors may be work which may be required to prepare notices of sale to be submitted with the application, to receive bids, or to prepare the contracts and bonds.

For sales which exceed the district forester's limit, the application, together with the report, estimate, map, and the supervisor's and district forester's recommendations, will be forwarded to the Forester for his approval. When the Forester has approved the application, the district forester will sign the notice of sale and proceed with the advertisement. After the contract has been properly executed cutting may begin, but the contract and bond should be forwarded to the Forester for approval, with extra copies for filing. The sale will then be handled as a district forester's sale, except that modifications of the contract can be made only with the Forester's approval.

Where advisable, a sample contract, unexecuted, containing all of the provisions of the proposed sale, may be submitted to the Forester in lieu of a formal application. When, however, the privilege of advance cutting is desired the applicant will in every instance be required to sign a formal application before his application for advance cutting will be considered. Upon approval of the sample contract by the Forester, the district forester will proceed with negotiations with the applicant and advertise the sale if its conditions are accepted by him. It is essential that no final assurances be given to prospective purchasers until the Forester has passed upon the application or sample contract.

ADVERTISEMENT.

Advertisement of sales of timber exceeding \$100 in amount is required by act of June 6, 1900 (31 Stat., 661), for a period of not less than 30 days.

Advertisements must be published in papers included in the yearly authorization issued to the supervisor by the Secretary of Agriculture. If publication in other papers is advisable, the authority of the Secretary should be requested through the Forester.

If the notice of sale is to be published in more than one newspaper, an original copy will be sent to each. The last day for receiving bids named in all the papers must be the same.

named in all the papers must be the same.

The notice of sale must announce the time and place of filing bids, the location and approximate amount of timber, the amount to be deposited, and the name and address of the supervisor from whom full information can be obtained. It will state that the right to reject any or all bids is reserved.

Great care will be taken to determine and designate closely the location of the timber which is advertised. If the land included in the notice of sale is unsurveyed, the word "approximately" should be inserted in the description of the probable legal subdivisions. Whether the land is surveyed or unsurveyed, the location should be given with reference to watersheds or well-known natural objects, as well as by legal or approximate legal subdivisions, so that if by any chance a mistake is made in naming the subdivision it will not be necessary to readvertise the timber.

The notice of sale of timber for which application has been made should take the following form, with such modifications as may be necessary by reason of varying requirements of the sale:

SALE OF TIMBER. (City.) (State.) (Date.)
SALE OF TIMBER. (City.) (State.) (Date.) Sealed bids marked outside, "Bid, timber-sale application, (Date of application.)
(Name of Forest.) "and addressed to the Forest Supervisor,
National Forest,
, "if class D sale), will be received up to and including the
(City.) (State.) day of, for all the merchantable dead timber standing or (Month.) (Year.)
down and all the live timber marked (or designated) for cutting by a Forest officer, located on an area to be definitely designated by a Forest officer before cutting begins,
including about acres in approximately sec, T, R,
M. on the watershed of River, within the
National Forest, estimated to be feet board measure of live saw (Species.)
timber, log scale, and cords of cordwood, more or less. No bid of less than
\$ per thousand feet board measure for saw timber and \$ per cord for
cordwood will be considered, and a deposit of \$ payable to the order of the
each bid submitted to the supervisor (or district forester). Timber upon valid claims is exempt from sale. The right to reject any and all bids is reserved. For further information and regulations governing sales address Forest Supervisor,
National Forest,
(Signature of forest supervisor or district forester.)

In order to make the advertisement legal, the last day for receiving bids must be at least 30 days from the first appearance of the advertisement, but need not be the date of its final appearance. Care should be taken, therefore, to see that the date up to which bids will be received, which the supervisor should insert in the copy to be furnished to the publisher, is the same day in the following month as the date of the first publication. If, however, the first publication appears on January 29, 30, or 31, the final date for receiving bids should be March 1, 2, or 3, as the case may be. If the first publication appears in February, the final date for receiving bids should be two days later in March than the date of the first publication. If in any case the last day for receiving bids falls on Sunday or a legal holiday, the final date should be the following day.

If material mistakes appear, they should be corrected and the date up to which bids will be received changed to the thirtieth day after the first appearance of the corrected advertisement. A full period of 30 days will

(Title.)

However, the total number of thus be allowed for submitting bids. times the notice of sale, whether correct or incorrect, is published should not exceed five.

If the notice of sale is to provide for the sale of only a part of the timber advertised, the notice should read, "for all Sale of a part of timber advertised. or any part of the merchantable dead timber standing or down and all of the live timber marked (or designated) for cutting, etc."

Timber for which there is likely to be a demand and which should be promptly cut for silvicultural reasons may be General notice. advertised by a general notice in advance of application to purchase, upon approval by the officer authorized to sell the amount of timber involved.

It is desirable to call the attention of prospective purchasers by such notices to timber which is insect infested, bodies of dead timber which are deteriorating, or timber the removal of which will benefit the Forest.

The advertisement for a general notice should follow the same form as the application notice, given above, with the following changes:

The words ''l	Bid, timbe	er sale a	ppli	(Date of application.)						
(Name of Fo		should	be	changed	to	"Bid,	timber	sale,		
general notice,	(Date)	,	(Na	me of Forest.)		•"				

Whenever a timber sale is to be advertised, the supervisor will issue to the publisher of the newspaper or other publica-Authority to pubtion in which the advertisement is to appear a Form BF "Authority to publish advertisement," which will be transmitted with the notice of sale and a copy of the advertising rate form. A copy of each Form BF issued will be retained.

In filling out Form BF, the designation of the case, name of Forest, date, name of paper, place of publication, and date and number of the Secretary's authorization must be inserted in the proper blank lines. Other data will be filled in as indicated by the italicized clauses of the following:

You are hereby authorized to publish the inclosed advertisement for proposals for

The publisher's attention will be directed to the fact that advertisements must be set up like the sample which appears on the second page of Form BF, since charges for display headings can not The matter must be set up solid, without paragraphing, and with the signature and title of the officer signing the advertisement "run in."

When the advertisement has run for the time ordered, the publisher of the newspaper will fill out the voucher attached to Form BF and transmit it, with an affidavit of publication, to the district fiscal agent. If the publisher's sworn rates are not already on file, these must accompany the account.

In order that large sales may be given all possible publicity, supervisors will, during the period of advertising, post copies of Form 975 where they will attract the notice of the general public.

BIDS AND AWARDS.

Instructions concerning deposits in connection with bids are given under "Payments, deposits, refunds, and transfers,"

page 27.

Envelopes containing bids will be stamped with the date of receipt and filed, unopened, by sales under the date of opening. At 2 o'clock p. m., on the day following the final date for receiving bids, all the bids submitted will be opened by the supervisor or district forester, as the case may be, in the presence of one or more witnesses. Bidders may be present at the opening of the bids if they desire. The original bids should be indorsed with the date opened and a list of those present. Bids for lower rates than those named in the notice of sale can not be considered. If no bids have been received, the applicant will be requested by the supervisor to submit a bid immediately.

The sale will be awarded to the highest bidder, unless such an award will create a monopoly, or unless the highest bidder is debarred from the use of the National Forest by his previous acts, or the public interest presents some unforeseen

objection to the sale.

Whenever practicable, timber for which more than one bid has been received may be allotted among several bidders at the highest price offered by any one of them or at such variations in price, in no case less than that stated in the advertisement, as will equalize differences in the quality or accessibility of the timber on different parts of the sale area.

If any portion of the timber is awarded to another than the applicant, a new timber sale record card will be filled out and filed by the

supervisor and also by the district forester in class D sales.

When the contract is returned, executed, the data on the timber sale record cards will be checked by the officer approving the sale and deposits made by unsuccessful bidders refunded in accordance with the instructions on page 28.

CONTRACTS.

The contract should not be submitted to the successful bidder for execution until assurance is received that the deposit

required with the bid has been made.

Every reasonable effort will be made by the supervisor to secure the prompt execution of all agreements and bonds. If for any reason the agreement and bond are not executed, the district forester will be notified and the case closed.

Form 202 will be used in the preparation of contracts, with the insertion of such special clauses as particular cases may require.

If two or more persons who are not partners purchase timber, the names of all will be given in full at the beginning of the contract and

all will be required to sign. The variation in form and requirements for execution when the sale is made to an individual, a partnership, or a corporation, or is a private sale are outlined on Form 202. Unless the contract provides for the sale of only a part of the timber advertised it will follow the advertisement absolutely in the description of the lands and the amount and location of the timber included in the sale.

Evidence of authority of the person who executes a contract or bond on behalf of a corporation will be obtained, and in every case submitted to the district assistant to the solicitor for approval as to its sufficiency. Such

evidence will be filed with the approved original of the contract.

As evidence of the authority of the officer signing for any incorporated company, whether purchaser or surety, a copy of, or extract from, the articles of incorporation, the by-laws, or resolutions of the board of directors, whichever it may be that authorizes the officer to execute the papers for the company, will be required. This copy or extract will be certified by the secretary of the company under the corporate seal in substantially the form outlined in Form 319.

The resolution indicated on Form 319 will be required in substan-

tially the following form:

It is resolved by th	e board of directors of the, that it is for (Name of company.)
Form of resolution. the	best interest of said company that(Name of president or other officer.
be authorized to exec may be drawn by said	(President, secretary, etc.) ute any and all instruments of any character whatsoever that company to the United States Government in any and all o or hereafter and until this resolution is duly revoked, and
(Name of officer.)	, of said (President, secretary, etc.)
(Name of company.)	, is hereby directed and authorized to execute and deliver

for and in behalf of said company and as its act and deed to the United States Government and any or all of its departments any and all instruments drawn by said company to said Government or any or all of its departments, and to affix to said instruments the corporate name and seal of said corporation.

When witnesses are required to the execution of any contract, if possible one will be a Forest officer and the other the notary public who takes the acknowledgment of the bond.

BONDS.

A bond will be required in all sales involving timber above \$3,000 in value, and in sales for smaller amounts when it is considered necessary by the approving officer to insure compliance with the contract.

The following table is not intended to establish a hard and fast rule in fixing the amount of bonds, but rather is to be used as a guide. When, because of special conditions, a larger bond is advisable the amounts given in the table should be increased.

Amount of sole.	Amount of bond.
\$3,000-\$5,000	\$500
5,000-10,000	1,000
10,000-20,000	2,000
20,000-30,000	3,000
30,000-40,000	4,000
40,000-75,000	5,000
Above 75,000	\$6,000-20,000

Form 377 will be used. The bond will follow the contract absolutely in its reference to the purchaser, the description of the timber, and the terms of the sale. It is essential that the date of the execution of the contract appear in the bond and that the bond be approved on the same date as the contract. The original only will be executed and will be filed with the original of the contract.

Under authority of the acts of August 13, 1894, and March 23, sureties on bonds.

1910, the Treasury Department issues lists of surety companies authorized to act as surety on bonds to the United States. Only the surety companies on these lists, copies of which will be furnished to district foresters, may be accepted. While surety companies rather than individuals are preferred, purchasers can not be required to furnish corporate surety. The Treasury Department determines the responsibility of the surety companies in the lists, but it is extremely important that the responsibility of individual sureties be established and made a matter of record. If the purchaser is a corporation or a copartnership, sureties other than its officers, stockholders, or partners will be secured.

The responsibility of individual sureties should be established by the signing of the "certificate of solvency" attached to the bond, Form 377, by a judge or clerk of a State court of record, a judge, clerk, or deputy clerk of a United States court, a United States attorney or one of his assistants, a United States commissioner or a

postmaster.

In accordance with the act of March 2, 1895 (28 Stat., 807), every bond should be examined by the district fiscal agent and the district assistant to the solicitor at least once every two years for the purpose of ascertaining the sufficiency of the sureties.

Evidence of the authority of a person signing a bond as principal or surety on behalf of a corporation will be secured in accordance with the instructions under "Contracts," page 23, and filed with the original.

ADVANCE CUTTING.

Applications for advance cutting will be discouraged, and will be approved or recommended only to prevent serious hardship or delay or unnecessary expense to the purchaser. Forest officers will encourage purchasers to

submit applications far enough in advance to make advance cutting unnecessary.

Form of application. The application for advance cutting will take the following form:

APPLICATION FOR ADVANCE CUTTING. (Case designation.) (Title of approving officer.) (Address.) SIR:, of ,, hereby (I or we.) (Name of applicant.) (City.) (State.) (Date.) under timber-sale application of (my or our.) do hereby, in consideration of the granting of said privilege, promise (I or we.) (United States depository), to be placed to the credit of the United States, in advance of cutting, a sum sufficient, in the judgment of the Forest officer in charge, to cover the estimated value of all such timber as may be cut under this application prior to notice of the award of the sale of the timber included in said timber-sale application; and to submit, in accordance with the directions in the notice of sale, based on said timber-sale application, a bid of not less than the minimum rate (or rates) named in said notice of sale, and further to pay said depository for all the timber cut as aforesaid, at not less than the minimum rate (or rates) named in the said notice of sale, or, if a bid higher than the minimum rate (or rates) is received, at the rate (or rates) of said bid. And further promise and agree to cut and remove said timber in strict accordance with all and singular the rules, regulations, and provisions set forth in said application and such modifications thereof as may be made by the approving officer. A deposit of dollars (\$....) has been sent to said depository to cover the estimated value of such timber as may be cut in advance as aforesaid. Signed in duplicate this day of 19... (Signature of applicant.) Approved at, under the above conditions, 19... (Signature of approving officer.)

All requests for advance cutting will be submitted to the Secretary for approval, through the Forester, in accordance with Regulation S-8. Requests by wire should state the amount, stumpage rates at which the timber will be advertised, and conditions creating an emergency. Upon approval of the request by the Secretary, the formal application will be approved by the

(Title.)

Forest officer having jurisdiction in accordance with the foregoing instructions.

Whenever it is probable that other bids besides that of the applicant for advance cutting will be submitted, sufficient timber should be advertised as far as possible to satisfy the other bids in the event that they exceed that of the original applicant. Awards of timber should, if practicable, be made to both the original applicant and to such other persons who may have outbid him, at the highest price offered by any bidder. The applicant for advance cutting must, however, be given first consideration in the award, provided that he will contract for all timber cut and to be cut at the highest price bid.

The permit for advance cutting does not give the applicant the right to take all the timber which he has applied for at the rate of the highest bid, but merely to take such timber as he cuts before the completion of the advertisement. In no case will he be allowed to cut timber in excess of the amount covered by his deposit. If the only bid received is from the applicant for advance cutting and it is accepted, the supervisor may allow cutting to continue after the expiration of the advertisement and until the contract is presented for execution if the deposits are sufficient. A bid must be submitted and the contract providing for payment at the highest price bid executed immediately, otherwise cutting will be suspended until these requirements are met.

PRIVATE SALE.

Contracts, including timber which has been advertised but for which no satisfactory bid was received or sales consummated, may be made at any time, through private negotiations, by the officer having authority to sell the amount of timber involved. The price must be not less than the highest price offered if any bid was received, and in no case less than the minimum named in the advertisement. The procedure in classes C and D sales will be followed, except as to advertisement.

SALE OF MATERIAL SEIZED.

In cases of seizure or recaption the seized material may be sold to the highest bidder. Where the value is over \$100 it should, if practicable, be advertised if this will result in securing a higher price. It is permissible, however, to secure informal bids, provided the full value of the material can thus be secured. No sale should be made without specific authority and instructions from the district forester, acting upon the advice of the assistant to the Solicitor.

PAYMENTS, DEPOSITS, REFUNDS, AND TRANSFERS.

Forest officers will see that no timber is cut or removed in advance of payment, and that a sufficient amount is always on deposit to insure against overcutting. In order that operations may not be delayed, purchasers will be notified in ample time when an additional payment is required. Failure to make prompt payment when requested is cause for suspending operations, provided the amount cut equals in value the amount on deposit or may do so before a second payment can be made. Requests for

postponement of payments can not be considered. In sales of \$100 or less the full amount in one payment will, wherever possible, be required in advance of cutting.

In determining the amount of deposits with bids and the size of payments in all but classes A and B timber sales the following schedule may be used as a guide, but may be increased to meet special conditions, such as a large daily cut:

Amount of sale.	Amount of deposit.
Under\$250	\$50
\$250-500	100
500-1,000	200
1,000-5,000	200-500
10,000-20,000	1,000
20,000-30,000	1,000
30,000-40,000	2,000
40,000-50,000	2,500
50,000-60,000	3,000
60,000-70,000	4,000
Above70,000	2,5,000

1 In even hundreds.
2 Or more, as required.

Money deposited to cover cost of advertisement and to secure advance cutting may be credited toward the amount to accompany bid. Deposits to cover cost of advertising and to accompany bids apply

on the first payment if the sale is awarded to the depositor, otherwise they will be refunded. If, however, an examination is made and timber advertised as a result of an application, and the purchaser fails to complete the sale, a sum sufficient to cover the cost of making the examination and advertising the timber may be retained, in the discretion of the officer approving the sale. Refunds to bidders will be made on vouchers prepared by the supervisor in class C sales and the district forester in class D sales.

If a purchaser who has deposited money in a timber sale afterwards violates any of the terms of his contract, an amount sufficient to cover damages thereby caused to the United States may be withheld

from a refund otherwise due the purchaser.

Purchasers who have complied with the terms of their contract and have cut all the designated timber from a sale area are entitled to a refund of any balance they may have on deposit. When a contract is canceled by mutual agreement, a refund of the amount not due the United States may be made provided the terms of the contract have been complied with. Generally speaking, all money not due the Government on any transaction will be refunded unless the purchaser has willfully neglected to remove his timber within the time specified or has been negligent in carrying out the terms of the contract. Sales will not be closed by supervisors while a balance is due the purchaser without filing a written explanation of the reasons on which the action is based unless the amount is \$1 or less. Refunds of \$1 or less will not be made unless the purchaser definitely requests it.

In cases in which a purchaser is entitled to a refund the supervisor will prepare a Form A voucher in duplicate. He will see that the amount and date of deposit and the amount and value of the timber cut are correct. When several deposits have been made the date

and amount of each will be given. The proper case designation will be given, so that the transaction may be identified with certainty. Refunds can be made only to the original depositor or his legal representatives, and in the latter case an exemplified copy of letters testamentary or of administration must accompany the voucher. The original will be executed by the depositor or his legal representative and the correctness of the amount certified to by the Forest supervisor, who will transmit it to the district forester for approval before payment.

When the executed original voucher is forwarded to the district forester by the supervisor, the latter should enter on the record card in the case the amount to be refunded as though the refund had already been made. No notice will be sent to the supervisor that the refund has been made. In case a voucher is not approved the supervisor will be notified by the district forester and the refund

entry should then be stricken off the card.

Deposits may be transferred to a payor's credit on another transaction of the same class, as from one sale to another, without a written request, but his written consent will be obtained to transfers between transactions of different classes. Deposits may be transferred to the credit of another person only with the written consent of the original depositor. Proper notations will, in each case of transfer, be made on the card records.

The following form, with required modifications, may be used whenever necessary:

(Case designation.)	
•	approving officer.)
	(Address.)
(I or we)	, of, purchaser of the (Name) (Town) (State)
	ove designated timber sale, National Forest, respect-
	have deposited in connection herewith the sum of (I or we)
is all the timber	designated for cutting on the area included in said sale, and that all contract have been fully complied with, therefore,
magazagt that the	(I or we) balance of \$, due as an overpayment in said sale, be transferred
(my or our)	credit on timber sale of (the) (of) (my or our) (his or their)
	on said National Forest.
Signed in dup	licate this day of, 19
	(Signature)
Approved at.	(City.) (State.) (Date.)
	(Signature of approving officer)
	(Midda)



Forest users, when asked to make payments, will be furnished by Forest officers with a form letter of transmittal properly filled out to be sent to the depository with the payment. A duplicate will be forwarded at once to the supervisor. Duplicates will be held in a promise file. When the original is received from the fiscal agent and the necessary record made, it will be forwarded to the payor, and the duplicate, with proper notation, returned to the ranger.

MODIFICATION OF CONTRACT.

Verbal modification prohibited. No Forest officer has or will be given authority to modify any agreement verbally.

Modification will be made to prevent unnecessary hardship to purchasers, subject to the restrictions stated in Regulation S-7. For example, when the purchaser fails to remove the designated amount of timber in the specified time through unavoidable circumstances, the modification of the contract may be considered, if not disadvantageous to the United States.

Postponement of payments.

Postponement of payments, however, will not be allowed

Consent of sure-

When a bond has been given, the consent of the sureties must be secured before any modification of contract is approved.

Evidence of authority. The necessary evidence of authority of the person who signs on behalf of a corporation shall always be obtained.

In all cases applications to modify contracts under the terms of Regulation S-7, will be submitted by or through the district forester to the district assistant to the solicitor for determination of the legality of such modification before it shall be approved.

The following form, varied as required by conditions, will be Form for modification of contracts in advertised

tion of contract. sales:

APPLICATION FOR MODIFICATION OF CONTRACT.

(Case designation.)	
(Forest officer who will app	prove modification.)
(Addres	s.)
(I or we.)	, of, (Name of applicant.)
State of, purc	haser of timber in the above-designated case,
National Forest, respect	fully request that clause of the agreement signed in
duplicate by,	, on the day of, 19, and approved by the
(Title of approvi modified to read as follow	
"	27

If this application is approved
said timber in strict accordance with all and singular the terms and provisions of the aforesaid contract, except as herein modified.
1 further agree that if this application is approved a certain bond exe- (I or we.)
cuted by as principal and
and as suret at,
on the day of, 19, and approved by the
insure faithful compliance with the terms of the aforesaid contract, shall bind (me or us.)
and said suret, and
Signed in duplicate this day of, 19
(Signature of purchaser.)
Witnesses:
•••••
Approved at, under the above conditions 19
72
(Signature of approving officer.)
(Signature of approving officer.)
(Signature of approving officer.)
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to
(Signature of approving officer.) 1 Omit when bond has not been given. (Title.)
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to the modification of agreement: sureties.
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to the modification of agreement: Sureties. CONSENT OF SURETIES. (Case designation.)
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to the modification of agreement: Sureties. CONSENT OF SURETIES. (Case designation.) KNOW ALL MEN BY THESE PRESENTS, That whereas we. (Name of surety must be same as in bond.) of, , and , of (City.) (State.)
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to the modification of agreement: Sureties. CONSENT OF SURETIES. (Case designation.) KNOW ALL MEN BY THESE PRESENTS, That whereas we
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to the modification of agreement: Sureties. CONSENT OF SURETIES. (Case designation.) KNOW ALL MEN BY THESE PRESENTS, That whereas we. (Name of surety must be same as in bond.) of, , and , of (City.) (State.)
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to the modification of agreement: **CONSENT OF SURETIES.** (Case designation.) KNOW ALL MEN BY THESE PRESENTS, That whereas we
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to the modification of agreement: CONSENT OF SURETIES. (Case designation.) KNOW ALL MEN BY THESE PRESENTS, That whereas we. (Name of surety must be same as in bond.) of, and, of, and, of, are sureties on a certain bond in the sum of dollars (City.) (State.)
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to the modification of agreement: SURETIES. (Case designation.) KNOW ALL MEN BY THESE PRESENTS, That whereas we. (Name of surety must be same as in bond.) of, and, of (City.) (State.) (\$tate.) (\$tate.)
(Signature of approving officer.) 1 Omit when bond has not been given. The following form will be used for the consent of sureties to the modification of agreement: Sureties. CONSENT OF SURETIES. (Case designation.) KNOW ALL MEN BY THESE PRESENTS, That whereas we (Name of surety must be same as in bond.) of, and, of, of, are sureties on a certain bond in the sum of dollars (City.) (State.) (\$\frac{1}{2}\$, are sureties on a certain bond in the sum of, and given to the United States of America by, of, are corporation organized and existing under (Address of purchaser.)

5276°—11——3



on the day of, 19, and approved by(Title of officer.)
on the day of, 19; and
Whereas the said
ment in writing dated the day of, 19, made application to the
to have that part of said contract reading (Title of officer who will approve modification.)
"
modified to read "", and has promised and agreed if said application is approved to cut and remove said timber in strict accordance with all and singular the terms and provisions of the aforesaid contract as modified by the conditions set forth in said application:
Now, therefore, we, the said
and, sureties as aforesaid, do hereby join in said application, and agree if the same is approved our bond shall bind us, our heirs, executors, administrators, successors, and assigns, and each and every one of us and them, jointly and severally, in the same manner as if said modification had been included in the contract to insure compliance with which our bond was given.
Dated at, this day of, 19 (Same date as execution of application.)
(Surety.)
(Surety.)
STATE OF
On this day of, 19, before me,
(Name of notary.)
a notary public in and for, residing therein, duly
sworn and acting under a commission expiring, 19, personally appeared
sworn and acting under a commission expiring, 19, personally appeared, known to me to be (Name of sureties.)
sworn and acting under a commission expiring, 19, personally appeared, known to me to be (Name of sureties.) the
sworn and acting under a commission expiring, 19, personally appeared, known to me to be (Name of sureties.) the
sworn and acting under a commission expiring, 19, personally appeared, known to me to be (Name of sureties.) the
sworn and acting under a commission expiring, 19, personally appeared, known to me to be (Name of sureties.) the

N. B.—The italicized words in the form of consent of sureties will be stricken out when executed by individuals and not by corporations.

Extension of time will not be granted for speculative purposes.

When an extension of time is favorably considered, the officer in charge should decide whether the present price is sufficient, whether the contract can be improved with particular reference to the present condition of the sale area, and if the method of marking, scaling, utilization, or sale administration can

Digitized by Google

be strengthened and improved by any modification in the agreement. Extensions of time without change in the other conditions of the contract will be granted only in cases where the interests of the United States will not be prejudiced thereby and then only when causes over which the purchaser has no control have unavoidably delayed his operations.

All extensions of time which bring the total cutting period allowed by the contract in excess of five years must be specifically approved by the Secretary.

When an extension of time is refused, any timber which may have been paid for and cut but not scaled at the date when the contract expires, may, in the absence of good reasons for retention, be scaled and its removal

by the purchaser permitted.

Whenever an extension of time is desired in an advertised sale an application should be made in accordance with the form for modification of contract, inserting after the words, "to read as follows," Clause 12 of the contract, Form 202, with the changes proposed. If the modification is proposed at an increase in price, the following should be added as part of the sentence following the modified clauses, "and further, to pay for all timber not cut during the time specified in said agreement at the rate

Consent of sureties will be obtained in the form given on page 31.

Postponement of When postponement of brush piling is advisable and is not provided for in the contract, the following change may be made in the form for modification of contract, after the name of the National Forest, line 3:

respectfully state that the snow is now too deep on the cutting area to permit of proper brush disposal, and therefore request that in accordance with paragraph (I or we.)

............of said contract we be permitted to proceed with the cutting and removal of the timber and to postpone brush disposal until such time as in the opinion of the Forest supervisor proper disposal of the brush can be made in accordance with the terms of the said contract.

......agree, if this application is approved, that.....will, as soon as (I or we.)

the condition of the snow makes it possible and not later than....., at the request of the Forest officer in charge of the work, put on a sufficient force of men to dispose of all brush caused by the operations subsequent to the granting of this application, and also all other brush which is not properly disposed of at the date of this application, in a manner satisfactory to the Forest officer in charge of this work, and to use every precaution against fire being started in such brush and débris as is not properly disposed of on account of the granting of this application and to pay for any damage that may result through the approval of this application.

If a bond is required at the time of postponement, the amount will be at least twice the estimated cost of brush piling, and will be prepared on Form 377.

Consent of suretles. The consent of sureties will refer to the application as follows:

 may proceed with the cutting and removal of the timber without piling the brush until

such time, not later than, as said Forest officers shall decide that the brush can be properly piled, and have agreed if said application is allowed that they will, as soon as the snow is gone, at the request of the Forest officer in charge, put on a sufficient force of men to dispose of all brush caused by the operations subsequent to the granting of said application, and also other brush of which disposal has not been made at the date of said application, in a manner satisfactory to the Forest officer in charge, and to use every precaution against fire being started in the brush and débris not piled on account of the granting of said application, and to pay for any damage that may be caused by the granting of said modification of the contract.

In unadvertised sales modifications will be granted only in writing, by letter, or by approval of an application in accordance with the foregoing forms if their use is deemed advisable. In advertised sales modifications will be

granted only by approval of a formal application.

Modifications will be approved by the officer having authority to make the class of sale the contract for which is to be modified, after the district assistant to the solicitor has advised that such modification is lawful. The application and consent of sureties should be

approved on the same day.

In unadvertised sales modifications will be prepared with two carbons, the original forwarded to the purchaser and the carbons filed with the supervisor and ranger. In advertised sales modifications will be prepared in quadruplicate and executed and approved in duplicate. A fifth copy will be prepared for the Forester's files in sales where the modification is approved by him. The original will be retained in the district forester's files in class D sales and in the supervisor's files in class C sales. The duplicate is for the purchaser, the third copy for the supervisor or district forester, as the case may be, and the fourth for the officer in charge of the sale. Dates and signatures should be filled in on all retained copies.

Consent of sureties will be prepared in duplicate but only the original executed. The original will be filed with the original of the application. The duplicate will be filed in the supervisor's office in class

D sales and the district forester's office in class C sales.

CANCELLATION OF CONTRACTS.

If the cancellation is by mutual agreement, an application executed by the purchaser and approved by the Forest officer approving the sale will be required except in unadvertised sales in which notification signed by the approving officer is sufficient.

Form for adverised sales.

The following form with necessary modifications will be used in advertised sales:

Case designation.)	
(Title of approving officer.)	
(Address.)	
Sir:	_
(I or we.)	, of
, purchaser of the timber in t (State.)	he above designated case by a contract
igned in duplicate by on the	day of, 19, and approved

Digitized by Google

by	, or (Title.)
· ·	• • •
the day of, 19, re	espectfully state that \dots have deposited in (I or we.)
connection therewith the sum of	f \$; that have cut thereunder (I or we.)
timber (of the value of \$; that all the terms of said contract have been
	account of the following circumstances(I or we.)
do not care to complete the sale:	••••••
	t the mid contract be canceled that
(I or we.)	t the said contract be canceled, that be
relieved from all further liability	thereunder, and that the sum of dollars
(\$) remaining to(My or our	credit be (refunded) (transferred to the credit.)
of	on timber sale of19)
Signed in duplicate thisday	y of 19
•	
Approved at, (City.) (State	,, , 19 te.) (Date.)
•	(Signature of approving officer.)
	(Title.)

The last part of the final sentence is necessary only when a balance is to be refunded or transferred.

If the cancellation is enforced, the action, which will be justified only on account of serious violation of the terms of the contract, will, except in Forester's sales, be taken only by the superior of the officer approving the contract and after the district assistant to the solicitor advises that such action is legal and after the purchaser has in writing been given a reasonable time to show cause why the contract should not be canceled. Formal notification of enforced cancellation will be sent in all cases, and, if by the district forester, will be sent through the supervisor with a duplicate copy for the supervisor's files.

Contracts will be canceled only after the condition and location of the cuttings, the amount of timber left uncut and the possibility of a ready sale at prices not less than those of the existing contract, have been reported on with specific recommendations. If enforced cancellation is considered, the report will in addition cover thoroughly the violation of the contract.

SPECIAL USES CONNECTED WITH SALES.

When special uses for sawmills, logging railroads, flumes, camps, etc., are to be used only in connection with a sale, provision for them. may be included in the timber sale contract.

PERIOD FOR REMOVAL.

The period allowed for cutting and removal will be governed by the amount of timber involved in the sale, the capacity of the mill, the practicable logging season, and the rate at which the timber cut can be disposed of in the available market. The period in class C sales should ordinarily not exceed three years. The approval of the Secretary must be secured in all cases where the period allowed by the contract exceeds five years.

In cases in which the contract requires the removal of a definite amount of timber each year, it may be advisable, because of preliminary work to be done by the purchaser, to make the amount for

the first year much smaller than for the following years.

The word "removed," as relating to timber sale contracts and to the closing of timber cases, will be construed to "Bemoved" de- mean that the timber is in such location that its further removal will neither interfere with the administration of the Forest nor require the attention of a Forest officer, nor interfere with any forest growth, nor be a fire menace, whether on or off the cutting area. When possible, the point of removal will be to roads or other places where the material is immediately available for distribution to consumers. With saw timber, removal to the mill can usually be required.

EXAMINATION OF TIMBER APPLIED FOR AND PREPARATION OF THE APPLICATION.

Upon receipt of an informal application for timber it The maximum anwill first be determined if the sale can be made without nual cut. exceeding the annual cut approved by the Secretary. If this is possible, the working plan, if one has been prepared for the area, will be checked to determine if a sale can be made On Forests working plans. with in accordance with its provisions. If decided in the affirmative, an examination of the timber will then be made to determine definitely the boundaries of the sale area, the provisions, including stumpage rates, which should be incorporated in the contract, and the best method for cutting unless it is already outlined. If necessary or advisable the estimates will be checked, but the fullest possible use should be made of reconnaissance maps and estimates.

If the sale can and should be made contrary to the provisions of the working plan, the approval by the district forester of the plan of the modification will be secured in all important sales. Approved changes

will at once be incorporated in the working plan.

Ordinarily it should be possible to determine from the preliminary plan if a sale can be made from the locality applied for, or if an attempt should be made to locate a sale area elsewhere. Changes suggested by applicants will be carefully considered, but can not be made when contrary to the best management of the Forest.

If the preliminary plan does not show clearly the advisability of

making the sale, an additional field examination must be made.

In any case unless full information is already at hand or from conclusive information available it is certain that the timber should not be sold, a detailed examination of the timber applied for will be made.

The problem of securing a future stand after cutting is the most important to be considered. Before any sale is The future stand. approved, clear-cut and definite directions will be prepared by the proper officer instructing the men in charge of the sale on marking the timber so that reproduction of the more desirable species will be secured. Each district should study the local species carefully so that the best silvicultural treatment of each type will be thoroughly understood. The results of these studies should be in the hands of all officers on National Forests.

Before making any timber sale the possible damage to reproduction

in cutting will be carefully considered.

If the reproduction is being or will be damaged by stock it may be advisable to recommend restriction of grazing for a Protection from time after cutting has been completed. In every case the supervisor will consider the possibility of arranging grazing allotments or periods so as to secure necessary protection for young growth without materially reducing the total number of stock grazed upon the Forest. If this is impossible, he should recommend necessary reductions. Grazing off the grass crop is a protection against fire which may offset damage from tramping. exclusion of stock from any locality will work a hardship on permittees it should not be recommended without carefully weighing all of the interests involved.

Before cutting commences the best method should be determined. Whether a clear cutting, selection, or group system or merely a light thinning is best can only be determined

after careful study on the ground.

Except in clear cutting, an approximate diameter limit or a statement of the percentage of the timber to be left is Approximate usually advisable to give the purchaser a rough idea of the amount of timber which will be removed. diameter limits are named, it should be understood that the stated limits may be varied as shown by the contract, in accordance with the silvical requirements of the stand, and that as a rule at least onethird of the volume of the original stand will be retained. limits will usually be adopted for different species in the same sale. The limit on desirable species should be high, in order to reserve from cutting a large percentage of young and healthy middle-aged trees for seed purposes and to provide for a second cutting within a reasonable time. For undesirable species, unless their percentage in the stand can be reduced in some other way, the limit will usually be low enough to remove all merchantable trees when not needed for protection of the soil or, in the absence of more desirable species, for seeding purposes.

Since it is usually undesirable to allow a purchaser to remove only All species to be cut. the best species, contracts will ordinarily provide for

the cutting of all merchantable species.

The method of logging and the seasons during which it will be carried on will be ascertained and their effect upon Logging methods. the Forest considered. If there is danger of serious damage to the reproduction or of erosion, the examining officer will recommend measures to prevent it.

Merchantable dead timber will be included in all sales. All dead timber will be disposed of as soon as possible, except Dead timber. in rare cases, where it constitutes the only available supply.

Digitized by Google

No sale will be so large as to endanger the future local supply.

If data are not available the future needs of the locality should be investigated. The limited supply on some Forests will prevent sales except for local use, but every effort will be made to satisfy legitimate demands.

Sales for large amounts will be made when necessary to encourage new purchasers, to establish new industries, to maintain established local industries, or to aid in local

development.

The size of a sale will in the main be determined by the cost of the improvements required to market the timber, with a view to restricting the necessary investment for such purposes per unit of material to be handled to a reasonable amount.

A sale may be apportioned at the highest price bid among different bidders, if desirable and practicable, to prevent

monopoly.

Classes A and B sales will usually be made by amount. Class C sales may include all the merchantable timber on a given area, which must be designated by unmistakable natural boundaries or by blazed lines. In either case, all small, isolated, and reasonably accessible bodies of timber, which if left would not be salable, will be included. Except where the cutting area is bounded by patented lands or valid claims, it is usually very undesirable to define the boundaries by legal subdivisions.

If the application includes all the timber on a watershed or slope the cutting area can be bounded by topographic features, such as ridges and streams. If only a part of the timber on a slope or watershed is wanted, the cutting area should not be limited to the most desirable. It is often better to cut one slope of a valley instead of the most accessible timber on both. When successive sales are made from the same watershed or locality the cutting areas will either be contiguous or so arranged that the timber left may be sold without difficulty.

In determining the cutting area for any large sale, small areas which will probably be needed to supply local demands must be excluded

and the lines plainly designated.

Timber included in a sale upon which mineral locations have been made after the execution of the timber-sale contract will be cut as Government timber. If the location was made after the application was received and before the contract was executed, and was evidently made to interfere with the timber sale, cutting must be suspended, but a report on the claim will be forwarded immediately to the district forester, who will at once report the matter to the chief of field division, with a request for speedy action to determine the validity of the claim.

It was decided by the United States circuit court for the district of South Dakota, in Lewis v. Garlock (168 Fed., 153), timber on mining that the United States may sell insect-infested timber from a mining claim that has not passed to patent when the timber is a menace to that on adjoining National Forest land. Accordingly Forest officers may dispose of insect-infested timber from unperfected mining claims when such timber is an actual menace to the Forest.

The following policy should govern payments for timber cut from

claims:

Whether the claim is apparently held in good faith or not, if timber is cut and removed payment will be made to the Government in all cases except where the timber is removed in good faith for the purpose of clearing the land for cultivation or for development, or where at the time of cutting the timber is actually needed by the claimant for use in making improvements on the land embraced in his entry or location. If any such claimant should need timber for the purposes above specified and should be unable to obtain it on his claim, he will be allowed to take timber under free use permit from other lands of the United States for these purposes up to the amount cut from the claim for which the United States has received payment.

Where the boundaries of a mining location are not specifically marked and there are practically no evidences of its existence, a sale of the timber on the area may be consummated notwithstanding subsequent protest of any party alleging the location of a mineral claim covering such

area prior to the sale.

The department will not attempt, without the consent of the claimant, to sell or cut timber from unperfected, subsisting claims within a National Forest except in emergencies arising from insect infestations.

Particular care will be taken not to sell or cut the timber from lands which after survey will be school or railroad lands, and from unclassified railroad sections within the primary limits of the grant.

No timber will be sold at prices lower than the minimum or higher than the maximum fixed annually by the Secretary for the species, grade, and location, without first obtaining the Secretary's approval. Appraisals higher than the maximum rates or lower than the minimum rates will be submitted to the Secretary for approval in accordance with the following instructions:

In all sales the stumpage prices will be based not upon local prices but upon the actual value of the timber. Timber on a gentle slope and within a mile of a drivable stream may be worth more than twice as much as equally good but less accessible timber. The Forest Service will not compete in price with timber from claims or land grants. The actual value will be determined by deducting from the value of the product the cost of logging and manufacture and a percentage of profit ranging from 10 to 30 per cent on the investment required in each 1,000 feet b. m. or other unit of quantity which is handled. The exact percentage will depend upon the size of the operation, the stability of market conditions, and the risk of loss involved.

The data necessary to determine the actual value of the timber will be carefully obtained in each case by the Forest officer making the examination. The value of the manufactured product will be reported, together with the prices of competing timber and the estimated profit to the purchaser at the stumpage price recommended. The cost of brush disposal, protection of young growth, close utilization, and logging only marked timber must be considered before deciding on the value of stumpage.

Stumpage rates will not be reduced for any purchaser on the ground that his methods of manufacture are imperfect and utilization incomplete. In recommending prices for sales to mining, power, or other enterprises for their own use, the cost of securing material from the nearest source outside the National Forest must be fully reported. Stumpage in regions where timber from outside sources can not enter into competition will be appraised on a reasonable basis, in accordance with rates received on other portions of the Forest, not at monopoly prices.

Merchantable dead timber has approximately the same market value as green timber and the stumpage rates will ordinarily be the same. In many cases it will be possible to simplify the scaling and administration of the sale by recommending an average price for all

species, and for both living and dead timber.

Timber of saw-log quality which will become accessible for that purpose within a reasonable time will not ordinarily be sold as cordwood or for other uses at less than saw-timber rates.

No application will be approved by any officer unless the report of the examiner shows definitely that the full market value of the

timber will be received.

Recommendations for the period to be allowed for the cutting and removal of the timber will be made. The facilities of the purchaser for completing logging within the time specified must be considered.

A careful study of market conditions should be made and necessary provisions for complete utilization included in the application. The individual tree must be utilized as closely as good business and fairness to the Government and the purchaser justify. The Service will insist on as complete use as possible even if the same financial returns might be obtained for less material. Purchasers will be assisted in every possible way to find markets for material not commonly used. The basis for distinguishing between merchantable and unmerchantable timber as well as for distinguishing between material to be put to different uses and sold at different stumpage rates will be determined.

If it is found that purchasers can use logs of odd lengths a suitable provision will be included in the application. Tables and scale

sticks for logs of odd lengths will be furnished upon request.

If it will be necessary to construct logging camps or other buildings, telephone lines, flumes, or roads, their proposed location and disposition when logging is completed will be determined. The value of these improvements to the Forest Service will be considered, for example, the use of buildings for administrative purposes. If the improvements are not bought or retained by the Forest Service in pursuance of the contract, the purchaser will be allowed a definite period after completion of the logging for their removal. If they are not removed within this period they become the property of the United States.

A careful study will be made of the precautions necessary to prevent fire. The clauses which will be included in the application in sales where special apparatus such as donkey engines are to be used will be determined. It will also be ascertained how many employees will be available for

fire fighting.

The data obtained in the examination will be forwarded to the supervisor in the form of a map, estimate, and report.

In all advertised sales recommendations for marking must accompany the report where departures from the general marking rules are necessary.

Every report upon timber recommended for advertisement must contain at least one map. This must show not only the proposed sale area, but also its location with reference to the surrounding Forest, topographic features, such as ridges, streams, and roads, proposed roads, camps, and mill sites, lands

under patent or claim, and surveyed lines, if any.

The map must include enough of the surrounding Forest to show that the timber applied for may be removed without rendering the surrounding timber inaccessible and unsalable. Burns, barren or open land, forest types, and the limits of merchantable timber on slopes will be shown so far as they affect the desirability of allowing the sale. Within the area applied for the forest type will be shown and the topography will be indicated in sufficient detail to demonstrate the ease or difficulty of logging the timber, and to show the natural boundaries of compartments or logging areas. In small sales one map will show all these data, so that maps for blocks are unnecessary the blocks being indicated by dotted lines; this map will be drawn to a scale of not less than 4 inches to the mile, and the forest atlas colors and symbols, as far as practicable, will be used.

Large tracts require location maps on a small scale, showing only the outline of the proposed cutting, the section lines or other location points, private lands, if any, and dotted lines to represent the accompanying block maps on a large scale. The latter may then be

numerous and large enough to show necessary detail.

The proposed cutting area, as recommended by the examining officer and covered by his estimate and description, whether or not he agrees with the applicant, must always be clearly defined on the map; so must every part for which there is a separate estimate, description, or important recommendation.

When reconnaissance maps are available, the preparation of other

maps in the field will usually be unnecessary.

The timber upon the definite cutting area recommended and shown on the map will always be estimated. If uncertain Estimate. conditions of sale or differences between the Forest officer and the applicant make it likely that the area recommended may be extended or reduced, estimates for both the larger and the smaller area are required; otherwise the cutting area will be fixed and estimated without reference to other lands. Where applications for adjoining timber are expected, and where the whole body could be most economically examined at one time, the work of estimating may include a large area so that subsequent sales can be made without further estimating. In such cases the estimate of the cutting area covered by the present application must be kept separate and an estimate and report submitted for each additional area which comprises a natural logging operation. The same methods will be followed in estimating large bodies of timber which are to be sold. Whenever the Forest on different areas requires different treatment or different stumpage prices, the details of the estimates and report should clearly show such differences.

When there is more than one forest type within the area ex-By separate types. amined, separate estimates for each type should be made.

The Forest officer will submit an estimate of the merchantable timber which will be left after logging under the plan of cutting proposed. This estimate will include seed trees, young timber which it is inadvisable to cut, and timber of sizes or species not desired by the applicant and which can properly be left.

It is essential that the estimate include the percentages of the Grades of material. different grades of logs or of the different grades of lumber which will be cut in order that the market value of the product and stumpage value of the timber may be determined.

The work of estimating will be done as carefully as conditions will allow. Only in the largest sales may less than 5 per Intensity. cent of the total area be actually estimated, and whenever possible a much larger percentage will be taken. Estimates will be conservative, but overcuts should not ordinarily exceed 10 per cent of the estimate.

The Forest description, which will follow the outline on Form 578a, will be in sufficient detail to show clearly all features of the proposed sale. Data on logging and milling costs must be complete in order that proper stumpage prices may be

determined.

When common names for trees are used the nomenclature in Bulletin 17, Check List of the Forest Trees of the United States, except as modified in Forest Trees of Momenclature. the Pacific Slope, will be used.

Where possible, Forest officers will explain to applicants on the Explanation and ground, and preferably before the formal application demonstration to applicants.

Supplicants of the regulations and the requirements of the regulations and the requirements of the regulations and the special conditions which will be recommended in the sale under consideration. The Forest officer who prepares the application will be held responsible for the applicant's clear understanding of its conditions. The purchaser, however, should not be assured that his application will be approved or that the contract will contain certain provisions, except by the approving officer himself.

The reliability of an applicant and his reputation in the community Reliability and will be ascertained. If he has previously made use of National Forest resources, his methods of business will he manufactured by the national forest resources. be reported.

It will be possible in many cases to get information regarding the financial standing of applicants from the Credit Rating Book of the National Lumber Manufacturers' Credit Corporation, a copy of which is furnished to each district office.

The application will follow, as nearly as possible, the form of the Application to follow terms of contract in order that the purchaser may fully understand from the first the exact conditions of the sale.

Formal application, when required, must be made in every instance by the person who proposes to purchase the timber. Sales to actual purchasers only. Applications will not be received from a person acting for an undisclosed principal. Advertised sales will not be made to an officer of a corporation in his capacity as an individual when the timber is intended for the use of the corporation and not his individual use.

The preceding discussion and the need of any of the following Special clauses for applications and contracts.

Special clauses will be carefully considered in the application. Necessary modifications. tions will be made in the clauses given which supplement those printed on Form 202:

(1) Both marked and dead trees which are considered a fire menace by the Forest officer in charge will be felled, but only such portions of them as are merchantable under the terms of this contract will be logged and paid for; this does not include trees or stubs too short or small to be merchantable under the contract.

(2) We agree, when called upon by the Forest officer in charge, to furnish a number of men, sufficient in the judgment of the Forest supervisor, up to the number of our entire logging crew, to burn the brush and débris resulting from the cutting, under

the supervision of the Forest officer.

(3) A fire line having a width of not less than feet shall be cleared by the purchaser of all inflammable material, except stumps, whenever required by the Forest officer, along the boundaries of the cutting area and around groups of seed trees; such fire lines shall be constructed in a manner that will be satisfactory to the Forest

(4) All engines and locomotives not burning oil for fuel used in logging on the National Forest shall be equipped with spark arresters that are satisfactory to the

Forest officer in charge.

(5) The purchaser will burn the slash at such times and under such conditions as the Forest officer in charge may prescribe. [To be inserted in sales where it is safe and practicable for the purchaser to burn slashings, particularly where the season permits burning slash as it is cut.]

(6) All donkey or other steam-power engines not burning oil for fuel shall be equipped with a spark arrester satisfactory to the Forest officer, a steam pump, 200 feet of serviceable 1-inch hose, 6 buckets, and a constant supply of the equivalent of 6 barrels of water; all such equipment to be suitable and available for fire-fighting purposes.

(7) The maximum scaling length of all logs will be 16 feet; greater lengths will be scaled as two or more logs. Upon all logs 3 inches additional length will be allowed for trimming; logs overrunning the specified length will be scaled as 2 feet longer. [Insert in all sales including saw timber, except where other specific terms are agreed upon. A greater overrun may be allowed when necessary in sales of large timber.]

(8) Scaling will be done as often as practicable in the judgment of the Forest officer while cutting is in progress, and copies or abstracts of the scale reports will be fur-

nished to the purchaser after they have been approved by the supervisor.

(9) All cordwood material will be piled in compact even stacks for measurement, as directed by the Forest officer.

(10) No timber fit for saw, mining, or tie timber or posts, in the judgment of the

Forest officer, will be cut into cordwood.

(11) All hewn ties whose widest diameter inside the bark at the small end exceeds inches and all with visible defect will be scaled as saw logs. The scaling diameter will be the widest measurement at the small end of the tie. Small hewn ties which are sound will be counted as to the M feet b. m.

(12) All marked or dead trees which contain one or more merchantable logs shall be cut. All logs that will saw out per cent of merchantable lumber shall be considered merchantable under the terms of this contract. (The per cent depending upon character of material and local market conditions. See discussion under "Merchantable material" (p. 52).)

(13) Tops will be used for mining timbers, cross-ties, posts and cordwood whenever

possible.

(14) If necessary, in the judgment of the Forest officer, exceptions in the height to which stumps are to be cut may be made in the case of swell butted, fire scarred, or otherwise defective trees; the stumps, however, will be cut low enough to include

their whole merchantable contents.

(15) Logs shall be decked or piled for scaling at places agreed upon with the Forest officer, with ends even on one side of the skidway or pile, and the length shall be marked on the small or scaling end of each log by the purchaser. Logs of different species or value shall, if required by the Forest officer, be decked or piled in separate piles.



(16) Green timber which will cut a log not less than inches in diameter at the top and not less than feet long, and for diameters over inches containing not less than per cent of merchantable lumber of any grade, and for smaller diameters not less than per cent of merchantable lumber of any grade will be considered merchantable. Dead timber which will cut a log not less than inches in diameter at the top and not less than per cent of merchantable lumber of any grade will be considered merchantable. [The diameters and per cents depending upon character of material and local market conditions.]

(17) If material suitable for saw timber in the judgment of the Forest officer is cut into cordwood, it shall be scaled and paid for at the same rate as if used for saw timber.

[To be inserted in sales which include both cordwood and saw timber.]

(18) Unmerchantable timber may be used free of charge for construction purposes

in connection with the sale.

(19) If donkey engines are used, the rigging shall be slung as far as practicable upon stumps, or marked trees, and when possible the grab hook shall be used in all cases rather than the wire choker.
(20) Camps, chutes, and other improvements will be removed from the sale area

within six months from the termination of the contract, and if not so removed will

become the property of the United States.

(21) Camps, flumes, roads, dams, bridges, chutes, and other improvements required in logging will be located as agreed with the Forest officer, and in accordance with

such conditions as he may prescribe.

(22) This contract is intended to provide for logging in the woods by means of Any other method of logging may be (Indicate whether by horses, donkey engines, etc.) employed only with the consent of the Forest officer approving this contract and under

such conditions and restrictions as may be agreed upon with him. [To be inserted especially where there is a probability of substituting steam logging for other methods.]

(23) Cutting will begin at a point designated by the Forest officer, and will be confined to the least possible area which will yield the amount specified in this agree-

ment. [To be inserted in all sales for a definite amount instead of for all merchantable timber on a given area.]

(24) All camp buildings and structures on the National Forest shall be located in a manner satisfactory to the Forest officers at a sufficient distance from any stream to prevent pollution of any city water supply.

(25) Not to exceed ... per cent of the merchantable timber [separate percentages to be designated for each species if advisable] will be reserved in marking. [Desirable in the larger sales to indicate definitely to the purchaser the proportion of the stand which he will be permitted to log.]

Special clauses, based on the recommendations of the Bureau of Entomology, will be inserted in contracts for the sale Clauses for insect- of insect-infested timber. These clauses must be infested timber. specific in requiring that trees be cut, peeled, or sawed and brush disposed of, as the nature of the infestation requires, at the time required by Forest officers and by specified dates of each year.

ADMINISTRATION OF SALES—GENERAL.

The chief objects of timber-sale administration are to obtain the best forest conditions possible and complete utilization, with a minimum cost to the Service and prompt attention to the purchaser's needs.

Actual participation where possible and at least frequent personal supervision by supervisors, deputy supervisors, and Forest assistants of all woods work is essential, as is also close supervision by the officer in charge in order that the purchaser may know from the first exactly what will be required of him and that his expenses may not be increased by delayed changes in method.

Small sales are as important from a silvicultural standpoint as larger ones, consequently the methods used in each class which affect forest conditions must be given Small sales. equal consideration. Small sales are more expensive proportionately

Digitized by Google

reducing costs is necessary. Scaling or measurement and woods work will not be conducted oftener than is essential to prevent unnecessary hardship to the purchaser and to insure compliance with the contract. Purchasers may justly be required to have cut for measurement or scaling amounts of timber which will make the visit of the Forest officer worth while, and may be expected to so arrange their business that more frequent visits will be unnecessary. The proper arrangement of dates for marking and scaling will result in great economy.

Forest officers should never lose an opportunity to reduce the cost or increase the efficiency of administering large sales if it will not defeat the objects desired. The more simple and definite the methods adopted, the less chance there is for poor work by Forest officers or misunderstandings by purchasers. The location of each year's cut must be carefully determined and, so far as possible, must cover average conditions for the whole sale. Since the proper administration of large sales depends largely upon the men placed in charge, supervisors will use the greatest care in their selection. Important work of this character will not be left to inexperienced men.

Forest officers in charge of sales will see that the conditions of the contract are complied with, and should such conditions seem unjust or unreasonable, will take the proper steps to secure such necessary modifications as are authorized under regulation S-7. No Forest officer has been or will be authorized to allow the violation of a contract. A Forest officer can not properly handle a sale unless he has a copy of the contract and is familiar with its terms.

Questions concerning logging methods, compliance with the contract, etc., will be taken up with the purchaser or his superintendent rather than with subordinate em-

ployees.

Cutting may not begin in any sale until the contract has been executed or an advance cutting agreement has been executed and approved, the timber designated, the necessary deposits made and the Forest officer in charge furnished with a copy of the contract. In unadvertised sales it must also be definitely known that the contract is or will be approved. In advertised sales, if other requirements are satisfied, cutting may follow the execution and need not await formal approval of the contract.

MARKING.

When the sale of any green timber is assured, the supervisor will see that all trees which are to be cut are marked or otherwise unmistakably designated for cutting. Where only dead timber is purchased and no living timber will be cut, or where patches are to be cut clean, Forest officers may, instead of marking or designating every tree for cutting, blaze and mark the boundary of the cutting area or patch and instruct the purchaser in the manner of cutting. Merchantable dead trees, about which there may be a question, will always be marked, except where the contract contains a clause providing for the cutting of all dead timber.

When the plan of marking is followed, standing timber must be marked "U. S." near the ground, so that every stump will show the Where snow may conceal the marking from the cutters, each tree must also be marked at a point several feet from the ground.

On thick-barked trees where chopping through to the wood means considerable extra work and expense, and where cutting is to take place in the near future, the bark may be blazed and stamped "U.S." Usually it is inadvisable to mark timber a long time in advance of cutting, but where this is necessary for any reason, officers should cut The marking must be such through to and stamp the wood plainly. that the stamp will be distinct at the time of cutting, and as long after

cutting as is necessary for inspection.

Timber should be marked when it can be done most economically; the work will not, however, be done too far in advance and the cut-over area will be watched for mistakes. In no case should timber be marked outside the area designated in the contract. In a sale for a definite amount, only timber enough to yield that amount will be marked. The marking will be done thoroughly, and no large groups of mature trees will be left on the area unless so isolated that the purchaser can not reasonably be required to log them.

The system of marking and the proportion of the timber to be cut should be carefully explained to purchasers by mark-Demonstration to ing sample areas before a sale is consummated.

the desires of purchasers must be very carefully considered, the silvicultural needs of the Forest must take precedence over other considerations, even at a sacrifice in present stumpage

Since the marking of green timber is the most important part of any sale, it is much better to demonstrate on the ground to the Forest officers who will do the work how the marking should be done than to send out written instructions and criticize the work after it is done.

Whenever possible in large sales, a marking board, consisting of the district forester, the chief of silviculture, and the Forest supervisor, will mark representative areas and establish the marking policy to be followed in the The action of the board will be binding upon Forest officers doing the marking, and no change will be made in the system without referring the matter to the district forester.

Personal marking by supervisors and deputies will take precedence over ordinary routine, and supervisors or deputies will assist in the first marking in important sales. Supervisors, either personally or through their depu-

uties, are expected to check the work of marking frequently enough

to make sure that it is being properly done.

Every advantage will be taken of the services of men with technical training, but men without timber-sale experience, Experienced men even if technically trained, will not be placed in for marking. charge of important marking projects.

The following instructions for marking are general, and can not all be applied in any specific case. Modified to meet General instruc- local conditions, they will serve as a basis for marking in all sales and in administrative and free use. district forester may wherever advisable supplement these instructions with detailed instructions for the types in the district.

It may be advisable to keep a record of the volume of the trees marked and of the trees left to secure an idea of the percentage of

timber reserved.

Marking in all sales must be such as will insure the best forest growth after cutting consistent with practicable General policy. logging operations. All other terms of the sale will be subordinated to this end. As far as type conditions permit, this marking should leave on the ground sufficient timber for a second cut within a period of 50 years or less. Even if clear cutting is necessary, usually not less than one-fourth of the original stand should be retained in groups of seed trees to insure complete restocking.

All mature and overmature trees will be marked, except when Mature and defective trees.

Mature and defective trees.

Mature and defective trees.

Required for seed or protection. Similarly, all trees which show such defects as punk knots, spike tops, bad crooks, low forks, fire scars, cat faces, or frost cracks, will be marked. The officer doing the marking will not be unreasonable in requiring purchasers to take defective trees, but as a general rule those which will yield one merchantable log will be

marked.

An approximate diameter limit, if one is given in the contract, will be flexible. Thrifty, rapidly growing trees of desirable species will not be marked, even if larger than the stated diameter. Defective trees of any size which can be utilized

will be marked, unless needed for seed or protection.

The need of an early second cut, as well as the necessity of rapidly cutting over all areas of mature and deteriorating timber so as to increase the rate of growth of the remaining stand, will be carefully weighed before deciding upon the method of marking to be employed. Where the danger of windfall is great only a light cutting may be advisable, or groups of seed trees may be left where individual trees would be wind thrown. Particularly conservative marking may be advisable to protect the watershed, to prevent erosion, to retain the scenic value of the Forest along important roads, and at the lower limits of types where heavy cutting might result in the encouragement of less desirable species. On steep slopes and exposed ridges the particular need for forest cover and the paramount value of trees as seed bearers must be given consideration. Where the system of cutting plans for a second cut within 20 to 50 years, enough timber should be left to make the second cut practical from a lumberman's standpoint.

Each tree will be left, when possible, with its crown free enough for vigorous growth. If usable, trees which have been badly crowded and have only small, sickly crowns will be marked unless needed for the preser-

vation of proper soil conditions or for other silvical reasons.

Seed trees must be left where there are not enough young trees to form a good stand in the future, and the trees Seed trees. which would otherwise be left are not sufficient in number to properly seed up the area. Seed trees should be thrifty and capable of bearing large quantities of seed at once. Occasionally it will be possible to use trees too misshapen or defective to be merchantable, but as a rule, young, thrifty, full-crowned trees, which will yield good lumber in the future, will be chosen. In mixed forests seed trees should be of the more valuable species, but poorer species are better than none. In situations where logging is difficult, the

possibility of logging individual trees will be considered.

Where partial reproduction is present, fewer seed trees should be left than where there are no seedlings. If there is danger that fire will run over the area, enough trees will be left to seed the ground fully, whether reproduction is present or not. Large openings will not be made where the future forest will suffer. A number of seed trees will always be left on the edge of openings, such as old burns, on the side from which the prevailing winds blow. Ridges should be marked very conservatively. Isolated, thrifty trees of desirable species should not be marked.

It is best to first decide which trees should be left, and then mark the trees to be removed. Where there is doubt whether a tree is needed for seed or protection, it should be retained. Defective trees of doubtful merchantable value should ordinarily be marked. Correct marking can only be determined after a careful study of local

types and species.

In dense stands of even-aged timber, particularly of species liable to wind throw, clear cutting may be the only practicable method. In such cases, compact groups or patches of timber, of sufficient size to be wind firm should be left at frequent intervals to insure restocking. The areas cut clean should never be so large as to endanger complete reseeding from the patches of timber which will remain. The latter should be located as far as practicable upon the higher ground and other points favorable to wide distribution of seed.

It is usually advisable for a Forest officer thoroughly familiar with the principles which have been followed in the original marking, to check the marking before the sawyers and loggers have left any area, in order to mark any trees which were obviously overlooked, or, better still, just before operations have reached an area, in order also to cancel the marks on trees which should be left.

Witness trees, or any trees blazed to mark the line of any official witness and line Government survey, will never be marked or other-

wise designated for cutting.

The policy in regard to cutting timber on claims, on pages 38 and Timber on claims. 39, will be observed in marking.

BRUSH DISPOSAL.

The best way to dispose of brush is not everywhere the same. Piling and burning will be required where the fire risk is great, otherwise the method promising the best silvicultural results.

If piling and burning is necessary, all lops and débris, including large chips made from hewing ties, will be piled at a safe distance from standing trees. The piles will not be made in groups of seedlings or young growth, against dead snags, near living trees, or on stumps, large tops or logs, but whenever possible in openings. Piles should be adapted to the size of

the opening in which they are made and sufficiently compact to kindle easily and burn cleanly. Limbs or trimmed tops too large to burn well need not be piled, but may be left on the ground to rot. The ideal pile is of medium size, conical in shape, compact, 5 to 7 feet in diameter at the base, and 4 or 5 feet high.

When brush can not be piled on account of snow, and the contract does not provide for postponement, the necessary modification should be granted by the proper Forest

poling. Postponement of modification should be granted by the proper Forest officer, in accordance with the instructions on page 33.

Brush will be scattered whenever this method promises the best

silvicultural results, unless there is serious danger of fire, or where there is dense timber or reproduction. The scattered brush should be dense enough to afford actual protection to seedlings from evaporation or trampling by stock and to the soil from erosion. Ordinarily brush will be lopped so as to lie not higher than 2 feet from the ground. Less careful work may be sufficient in openings where the object is to keep cattle or other stock away from expected reproduction.

Ground burning may be advisable where clean cutting has been employed, to expose the loose, mineral soil for better

seed germination.

Where ground burning is adopted, the brush and débris will be left unpiled until conditions make it safe to burn the entire slashing. To follow this plan the agreement must require the purchaser to clear a fire line around the area to be burned and around all patches of timber within it which are to be left, and to furnish adequate help to the Forest officer who supervises the burning.

Frequently the most economical way to dispose of brush, if weather conditions are suitable, is to burn it as the cutting progresses. Fires can be started at convenient points and the brush thrown on them as it

is lopped. This is often feasible after light snow falls.

Brush burning is necessary whenever there is danger of fire, but ordinarily is not advisable over an entire sale area.

It is frequently possible to burn the brush so as to form broad fire lines, particularly along railroads or

wagon roads, laid out so as to do the least injury to young growth. Fire lines will ordinarily follow ridges rather than canyons and will be laid out according to the topography. Where to burn brush completely means damage to reproduction, unburned piles will be left, if they are not too close together. The effect of burning on grazing and future reproduction will be carefully weighed.

The best times for brush burning are after a light fall of snow or rain, early in the spring before the snow has melted or the dry season has begun, or during or immediately

after summer rains.

The proper method of disposing of brush from insect-infested trees must depend upon the habits of the insects by which trees are attacked. The brush from fungus or mistletoe infected trees which constitute a menace will be burned.

Brush disposal must always keep pace with logging, except when the depth of snow or other adequate reasons make Rate of disposal. proper disposal at the time impossible. Frequent inspection is necessary to see that the contract is being fulfilled in this respect.

District foresters will, wherever necessary or advisable, issue more Detailed instructions for the disposal of brush in

types found in the district.

SCALING.

Unless timber is sold on the basis of an estimate, as is occasionally done in timber settlement, it must be scaled, counted, or measured before it is removed from the cutting area, or from the place agreed

upon for the scaling, counting, or measuring.

All saw timber will be scaled by the Scribner Decimal C log rule. This rule drops the units and gives the contents of a Scale rule. log to the nearest 10. When the total scale of a log is desired, all that is necessary is to add one cipher to the sum of the numbers read from the scale stick, excepting the contents of 6 and 8 foot logs, 6 and 7 inches in diameter. These are given as 0.5, which multiplied by 10 gives 5 feet as the actual contents.

In the absence of a scale stick, or where the position of logs in the pile makes its use difficult, the diameters and lengths may be tallied

and the contents figured from a scale table later.

In order to decrease cost, purchasers may be required to skid logs for scaling, unless the cost of logging will be greatly increased by such requirement. Whenever this requirement is made it should be covered by an

appropriate clause in the contract.

The Forest officer should always insist on having one end of piles or

skidways even, so that the ends of logs may be easily reached.

When necessary and possible, the purchaser will be required to mark top ends of logs to avoid question when they are scaled in the

Each log scaled must be numbered with crayon. The number will be the same as that opposite which the scale of the

Numbering logs. log is recorded in the scale book.

The logs in all skidways must be counted, and the Check on total number of logs. number in each pile checked with the entries in the scale book.

Each merchantable log after scaling will be stamped "U. S." on at least one end. Logs so defective as to be unmer-Stamping logs. chantable will not be stamped, but will be marked "Cull."

On all National Forests except those in Alaska and west of the summit of the Cascade Mountains in Washington and Log lengths in Oregon, logs over 16 feet long will be scaled as two or more logs, if possible in lengths not less than 12 feet.

The following table shows how the lengths may be divided when scaling logs 18 to 60 feet long. The number of inches to be added to the diameter at the small end of each log, to cover taper, is placed under each length.

For example, a 42-foot log 16 inches in diameter at the top would be scaled as-

One 12-foot log with a diameter of 16 inches. One 14-foot log with a diameter of 17 inches. One 16-foot log with a diameter of 19 inches.

Total length, feet.	Butt log.	Sec- ond	Third		Motol lameth foot			I I	
Total length, feet.		log.	log.	Top log.	Total length, feet.	Butt log.	Sec- ond log.	Third log.	Top log.
18feet	10			8	40feet	16	12		1:
Increase inches	1			0	Increaseinches	3	1		
20feet	10			10	42feet	16	14		1
Increase inches	1 1			.0	Increaseinches	3	16		
Increase inches	12			10 0	44feet Increaseinches	16 3	10		1
24feet	14			10	46feet	16	16		1
Increase inches	14			10	Increase inches	10	2		1
26feet	14			12	48feet.	16	16		1
Increase inches	i			า๊ก	Increase inches	4	2		•
28feet	14			14	50feet.	14	12	12	1
Increase inches	2			Ō	Increaseinches	4	3	1	_
30feet	16] .	14	52feet	16	12	12	1
Increase inches	2			0	Increaseinches	4	3	1	
32feet	16			16	54feet	16	14	12	1
Increase inches	2			0	Increaseinches	5	3	1	
34feet	12	12		10	56feet	16	16	12	1
Increase inches	3	1 .1		.0	Increaseinches	5	3	1 1	
36feet	12	12		12 0	58feet	16 5	16 3	14	1
Increase inches	14	1 12		12	Increaseinches	16	16	2 14	
Increase inches	14	12		12	Increase inches	10	16	14 2	1

This table is intended to be used simply as a guide. The allowances

for taper should be varied to conform to the actual taper.

On the National Forests in Alaska and west of the summit of the Special rule for Alaska and west alope of Cascades. Cascade Mountains in Washington and Oregon, logs up to and including 32 feet long will be scaled as one log; lengths from 34 feet to 64 feet, inclusive, will be scaled as two logs, dividing them at the center as near as may be in even feet; for example, a 34-foot log will be scaled as an 18-foot and a 16-foot top log. The diameter of the larger log may be determined by taking the average of the top and butt diameters of the whole length or by calipering or estimated by the scaler with the help of a taper table. A 36-foot log will be scaled as two 18-foot logs. This does not apply to lengths including rapidly tapering butt cuts. The lengths and tapers for such logs can be judged by the scaler. Greater lengths than 64 feet will be scaled as three logs, making the divisions as nearly equal as possible and in even feet, and increasing the diameters according to the taper of the log.

When the logs are scaled as two or more logs, the scale allowed for the separate lengths will be added and the total sum recorded as one

While no hard and fast rules can be given or followed, certain general principles may be laid down. They must, however, be used with judgment by the scaler and varied wherever the conditions demand. Among the Factors considered points which must be considered are the size and shape of the logs, the quality as affected by various kinds of defects, the size and location of defect, and the requirements and limitations of markets.

It is assumed that purchasers utilize the maximum amount of Unnecessary loss material in manufacture. Since the Government can not be held responsible for loss caused by poor equipment or poor management, the scaler should not take them into consideration.

Loss may be caused by too thick slabbing; cutting material too thick or too wide at the main saw; poorly "sized" lumber; excessive "crowding" by the sawyer; poorly kept saws which "run;" waste in edging and trimming through ignorance or carelessness; sawing for a certain class of material regardless of the quantity of waste this

It is important that measurement of lengths be made frequently Measuring log enough to be sure that logs do not exceed the allowance for trimming specified in the contract.

If the scaler finds frequent violations, he will measure every log, and all logs found overrunning the trimming allowance will be scaled as if 2 feet longer, or 1 foot longer where the contract provides for odd lengths. Penalty scaling will be noted in the scale book against the number of the log so scaled to avoid possible controversy.

Frequent measuring is especially important on small sales where a Forest officer is not always present, because sawyers are more apt to be lax in measuring than when an officer is daily checking lengths.

Logs will be scaled in odd lengths if provided for in the contract.

All diameters will be measured inside the bark at the top end of Finding diameters. the log. If logs are not round, scalers will average the greatest diameter inside the bark at the top end of the log with the diameter at right angles to this. The necessary reduction in diameter will be made for swelling at the scaling end of a log when no lumber can be produced from it.

Diameters will be rounded off to the nearest inch above or below

the actual diameter.

Any portion of a log which contains a fault which prevents its manufacture into merchantable lumber is cull, and will not Defects in logs. be scaled and charged to the purchaser.

The following defects are most common:

Uniform center or circular rot, circular shake, pin dote, ground or stump rot, cat face, dote at side of log extending to the bark, burns or defect caused by lightning extending along side of log, defect caused by lightning extending along the log in spiral form, punky or soft sap, deep checks or seams, dote appearing in knots, curve, or sweep, crooks, crotches, and blue sap.

In general, a log containing sufficient sound material to saw out salable lumber equal to one-third of its contents as given by the scale rule is termed "merchantable."

This will be varied in accordance with the character

of the timber and local market conditions.

The term "sound material" is here used to signify such material as will produce lumber grading not below No. 3 common, or the lowest grade commonly merchantable in the markets supplied. Supervisors will, wherever advisable, furnish scalers with specifications of No. 3 common lumber, or the lowest grade commonly merchantable, from the grading rules of the recognized lumber associations in the vicinity of their Forests. The scaler is not expected to be a grader, but the grading rules will assist him in determining where to draw the line between merchantable and unmerchantable timber.

Under uniform center or circular rot may be included circular "heart rot" or any dote that may be roughly included within a circle on the cross section showing at either end of a log, making all of the log within the circle unmerchantable. In sawing, this area of defect is squared. The accompanying table shows the amounts of lumber which are lost in defects of this type, in diameters of 2 to 12 inches in the more common log lengths, and which should be deducted from the full scale of the log. Amounts for shorter or longer logs can be obtained as follows: For 6 or 8 foot logs, deduct one-half the amount of loss, which is the same for defect of a given diameter in a 16-inch log as in one of 30-inch diameter.

The actual loss caused by uniform circular rot as shown by the diagram, is also shown in accordance with the rules of adding 2, 3, and 4 inches, respectively, to the diameter of the defect, and deducting from the full scale of the log an amount equal to the contents of a log of the

resultant diameter.

Diameter of defect.	Loss shown by diagram. Log lengths—			By adding 2 inches. Log lengths—				By adding 3 inches. Log lengths—				By adding 4 inches. Log lengths—				
																10
	2 inches. 4 inches. 6 inches. 8 inches. 8 inches. 10 inches. 110 inches. 12 inches.	3½ 13½ 25 46¾ 66¾ 100	4 16 30 56 80 120	183 35 653 933 140	51 213 40 743 1063 160	10 20 30 50 70	10 20 30 60 90	10 20 40 70 100	10 30 60 80 110	10 30 40 60 90	20 30 40 70 110	20 30 50 80 120	30 40 70 100 140	20 30 50 70 100	20 30 60 90 120	20 40 70 100 140

By referring to the table it will be seen that the following rules can be used to obtain the desired results:

For uniform defect.3 inches or less in diameter deduct 10 feet b. m.

in logs up to 16 feet in length.

For defect 4 to 6 inches in diameter add 3 inches to actual diameter of rot, and deduct from the full scale of the log an amount equal to the contents of a log of the resultant diameter.

For defect 7 to 12 inches in diameter add 4 inches to diameter of rot and deduct an amount equal to the contents of a log of the result-

ant diameter from full scale of log.

Only experience gained by actually seeing defective logs "opened" at the saw will enable scalers to judge how far into a log defect extends when it appears only at one end.

In short logs showing defect less than 4 inches in diameter at only one end and not in the knots deduct one-half the amount called for by

the rule for the full length of the log.

In measuring the diameter of this type of rot the scaler should measure it at the end of the log showing the greatest area of defect, since the saw cuts in straight parallel lines. The rule given for circular rot may be used in determining the amount of loss caused by shake by finding the diameter of the portion of the log included within the outer "ring" of shake. If there is at the center of the log a core of sound timber of merchantable size, inside of the shake "rings," the core will be scaled as a log and the difference between its contents and the amount to be deducted is the net deduction from the full scale.

Pin dote appears on the cross section at the end of a log in the form of little rotten spots usually scattered in a roughly circular area. Logs containing it may "open up" poorly, the doty spots frequently converging and forming a mass of poor material. It sometimes extends into knots, and generally, if the visible area affected is 4 or more inches in diameter, it should be deducted as in circular rot.

Ground or stump rot is found in butt logs, usually appearing in the form of brown, dry punk. It seldom extends far into the log, and usually tapers to a point. If it joins center rot from above, the defect falls within the center or

circular rot class.

Where stump rot occupies the center of the log to within a short distance of the bark, a sufficient deduction can be made from the length of the log. In addition, a small allowance for the defect may also be made, since it may occur in the log above the section dropped. The responsibility of the sawyers in butting unusually defective logs and in adjusting log lengths so as to eliminate defect should be determined before scaling.

The scaler must exercise judgment in such cases, considering the relative diameter of the defect as compared with the diameter of the butt and sighting along the log to see if any boards can be cut between the rot and the bark. Where this defect occurs at only one side of the butt, it usually extends only a short distance into the log, and frequently much of it will come out in the slab, espe-

cially where there is considerable "flare" or swell.

Deductions for cat face can be determined by dividing a log into sections as follows: Consider what proportion of the length of log is affected; find the contents of this section on a scale stick, then determine the proportion of the section

that will be lost in sawing, and deduct this amount.

For example, in the butt of a 16-foot log with a top diameter of 24 inches, which scales 400 feet b. m., there is a large cat face about 5 feet long which extends to the heart of the log. The cat face tapers toward its top, where it will come out in slabbing, and affects about 4 feet of the log. The 4-foot section affected will contain one-fourth of the log scale, or 100 feet b. m. The defect includes one-half of the 4-foot section, or 50 feet b. m., which should be deducted. Here again judgment must be used. While the defect may extend to the heart at the point of cutting on the stump, it may taper rapidly toward its top and perhaps affect only one-third or less of the section.

The scaler should never lose sight of the fact that the percentage of loss caused by defects located at the side of a log is much less than when they occur near the center, since in the former case much of the defect will come out in slabbing. This is especially true of the butt of

the first log where the flare or swell is considerable at the point of

cutting.

In culling for dote on one side of a log extending to the bark, burns or other defects caused by lightning extending along the side of the log, the scaler should consider how far toward the heart they extend, and by estimating the percentage affected determine upon suitable deductions.

Since they do not usually run deep and can be mostly removed in slabbing, defects caused by lightning extending spirally along a log do not affect the scale. The percentage of loss is proportionately greater in small logs than in large ones.

Where a shell of unsound sap occurs, only the sound heartwood will be measured. Punky or unsound

Sound blue sap does not render a board unmerchantable, but the scaler should be certain that it is not insect eaten. Blue sap. The fault occurs most frequently in dead trees, but may sometimes be found to affect dying trees. Oftentimes logs containing it are slightly punky at the outside, and as a rule, if

the scaler in measuring the diameter includes the sap on one side of the log only, discarding the other sap, the result will be satisfactory.

Deep checks or seams are usually found in dead and dry trees and affect the scale in varying degree, depending upon the Deep checks or number of checks, their depth, etc. Almost always they extend through the sap and frequently into the Where they affect the sap alone, the rule for culling heartwood. for defective sap will apply; where the checks are small, it is fairly certain they affect the sapwood only; but when they are of considerable width they usually affect the heartwood, and proper deductions should be made.

Where only one deep, straight check occurs in a log the loss is very small, but where many seams are found the method given for use in

the case of deep spiral checks can be followed.

Where deep spiral checks are found, the scaler will measure the diameter of the portion of the log included within the checks. spiral largest circle which can be described on a cross section without being materially affected by the checks and class as defective all that part of the log outside the area defined by the circle.

Rot in the log is sometimes shown only by an examination of the Dote appearing in knots, and the only method of determining the proper

deduction is to see such logs "opened up."

When rot appears at the ends of a log and also in the knots, the deduction depending on the number of knots affected, their size, position, etc., should be from 10 to 50 per cent greater than when it appears at the ends alone. When dote appears in the knots, it indicates that the area of rot enlarges in the portion of the log near the

The percentage of a log affected by sweep or curve varies according to the diameter of the log. An amount of curve that might cull a very small log would not necessarily Curve or sweep.

cause the rejection of a larger log.

The scaler should, when possible, sight along curved logs, noting where the saw would square the log sufficiently to enable boards to



be cut on both sides affected by the curve, thus determining the amount of loss caused by the sweep. It should be remembered that boards sawed near the slab are always narrower and contain fewer board feet than those sawed from the balance of the log.

No deduction should be made for curve or sweep in logs over 16

feet long.

Except in rare cases, crotches do not affect the scale of logs sufficiently to require deductions. If sawyers do their work properly they will cut back on the log sufficiently to eliminate the part affected by the crotch.

The scaler should obtain the average diameter of the log imme-

diately below the enlargement caused by the crotch.

Scribner Decimal "C" Log Rule. FOR LOGS UP TO AND INCLUDING 32 FEET IN LENGTH.

[Contents of logs.]

					•			<u>.</u>						
Diameter in inches.	Length (feet)—													
	6	8	10	12	14	16	181	20	22	24	26	28	30	32
6	Board feet. 0.5 0.5 1 1	Board feet. 0.5 1 1 2 3	Board feet. 1 1 2 3	Board feet. 1 2 2 3 3	Board feet. 1 2 2 3 4	Board feet. 2 3 3 4 6	Board feet. 2 3 3 4 6	Board feet. 2 3 3 4 7	Board feet. 3 4 4 5 8	Board feet. 3 4 4 6 9	Board feet. 3 4 5 6	Board feet. 4 5 6 7	Board feet. 4 5 6 8 11	Board feet. 5 6 7 9
11	2 3 4 4 5 6 7 8 9	3 4 5 6 7 8 9 11 12 14	4 5 6 7 9 10 12 13 15	4 6 7 9 11 12 14 16 18 21	5 7 8 10 12 14 16 19 21 24	7 8 10 11 14 16 18 21 24 28	8 9 11 13 16 18 21 24 27 31	8 10 12 14 18 20 23 27 30 35	9 11 13 16 20 22 25 29 33 38	10 12 15 17 21 24 28 32 36 42	11 13 16 19 23 26 30 35 39 45	12 14 17 20 25 28 32 37 42 49	13 15 18 21 27 30 35 40 45 52	14 16 19 23 28 32 37 43 48 56
21	12 13 14 15 17 19 21 22 23 25	15 17 19 21 23 25 27 29 31	19 21 23 25 29 31 34 36 38 41	23 25 28 30 34 37 41 44 46 49	27 29 33 35 40 44 48 51 53 57	30 33 38 40 46 50 55 58 61 66	34 38 42 45 52 56 62 65 68 74	38 42 47 50 57 62 68 73 76 82	42 46 52 55 63 69 75 80 84 90	46 50 57 61 69 75 82 87 91	49 54 61 66 75 82 89 95 99	53 58 66 71 80 88 96 102 107 115	57 63 71 76 86 94 103 109 114 123	61 67 75 81 92 100 110 116 122 131
31	27 28 29 30 33 35 39 40 42 45	36 37 39 40 44 46 51 54 56 60	44 46 49 50 55 58 64 67 70 75	53 55 59 60 66 69 77 80 84 90	62 64 69 70 77 81 90 93 98 105	71 74 78 80 88 92 103 107 112 120	80 83 88 90 98 104 116 120 126 135	89 92 98 100 109 115 129 133 140 150	98 101 108 110 120 127 142 147 154 166	106 110 118 120 131 138 154 160 168 181	115 120 127 130 142 150 167 174 182 196	124 129 137 140 153 161 180 187 196 211	133 138 147 150 164 173 193 200 210 226	142 147 157 160 175 185 206 214 224 241
41	48 50 52 56 57 59 62 65 67 70	64 67 70 74 76 79 83 86 90 94	79 84 87 93 95 99 104 108 112	95 101 105 111 114 119 124 130 135 140	111 117 122 129 133 139 145 151 157 164	127 134 140 148 152 159 166 173 180 187	143 151 157 166 171 178 186 194 202 211	159 168 174 185 190 198 207 216 225 234	175 185 192 204 209 218 228 238 247 257	191 201 209 222 228 238 248 260 270 281	207 218 227 241 247 258 269 281 292 304	223 235 244 259 266 278 290 302 314 328	238 252 262 278 286 297 310 324 337 351	254 269 279 296 304 317 331 346 359 374
51 52	73 76	97 101	122 127	146 152	170 177	195 202	219 228	243 253	268 278	292 304	315 329	341 354	365 380	389 405

Digitized by Google

Scribner Decimal "C" Log Rule—Continued.

Diameter in inches.	Length (feet)—													
	6	8	10	12	14	16	181	20	22	24	26	28	30	32
	Board feet. 79	feet.	Board feet.	Board feet.	Board feet.	Board feet.	Board feet. 237	Board feet. 263	Board feet. 289	Board feet.	feet.	feet.	feet.	Board feet.
53	79	105	132 137	158	184	210	237	263	289	316	341	368	395	421
54	82	109	137	164	191	218	246 255	273 283	300	328	355	382 397	410 425	437 453
58	85 88	113 118	142 147	170 176	198 206	227 235	264	294	312 323	340 353	368 382	411	441	470
57	91	122	152	183	213	244	274	304	335	365	396	426	457	487
58	95	126	158	189	221	252	284	315	347	379	410	442	473	505
53	98 101	131 135	163 169	196 203	229 237	261 270	294 304	327 338	359 372	392 406	425 439	457 473	490 507	523 541
61. 62. 63. 64. 65. 66. 67. 68. 69. 70.	105	140	175	210	245 253	280	315	350 362	385	420	455	490 506	525	560
63	108	145 149	181	217	203	289 299	325 336	373	398 411	434 448	470 485	523	542 560	579 597
64	116	154	193	224 232	261 270	309	348	373 387	425	464	503	541	580	619
65	119	159	199	239	279	319	358 370	398	438	478	518	558	5 97	637
66	123	164	206	247	288	329	370	412	453	494	535	576	617	659
67	127	170	212 219	254 262	297 306	339 350	381 393	423 437	466 480	508 524	550 568	593 611	635 655	677 699
60	131 135	175 180	226	271	316	361	406	452	497	542	587	632	677	723
70	139	186	232	279	325	372	419	465	512	558	605	651	698	744
-	1	192	240	287	335	383 395	430	478	526	574	622	670	717	765
73	148 152	197 203	247 254	296 305	345 356	406	444	493 508	543 559	592 610	641 661	691 712	740 762	789 813
74	157	209	261	314	366	418	471	523	576	628	680	712 733	785	837
75	161	215	269	323	377	430	484	538	592	646	700	754	807	861
<u>76</u>	166	221	277	332	387	443	498	553	609	664	719	775	830	885
77	171	228	285 293	341	398	455 468	511 527	568	625	682 702	739	796 819	852 878	909
79	176 180	234 240	301	351 361	410 421	481	541	585 602	644	722	761 782	842	902	936 963
71	185	247	309	371	432	494	556	618	680	742	804	866	927	989
81		254 261	317 326	381 391	444 456	508 521	572 586	635 652	699 717	762 782	826 847	889 912	953 977	1,016 1,043
83	201	268	335	401	468	535	601	668	735	802	869	936	1,002	1,069
84	206	275	343	412	481	549	618	687	755	824	893	961	1,030	1,099 1,123
85	210	281	351	421	491	561	631	702	772	842	912	982	1,052	1,123
80 87	215	287 295	359 368	431 442	503 516	575 589	646	718 737	790 810	862 884	934 958	1,006	1,077	1,149
88	221 226	301	377	452	527	603	678	753	829	904	979	1,031 1,055	1, 105 1, 130	1,179 1,205 1,232
89	231	308	385	462	539	616	693	770	847	924	1,001 1,023	1,078	1, 155	1,232
		315	393	472	551	629	708	787	865	944	1,023	1,101	1,180	1,259
91 92 93 94 95	241 246	322 329	402 411	483 493	563 575	644 657	725 739	805 822	886 904	966 986	1,047 1,068	1,127 1,150	$1,208 \\ 1,232$	1,288 1,315
93	251	335	419	503	587	671	754	838	922	1,006	11.090	1.174	1,257	1.341
94	257	343	428	514	600	685	771	857	942	1,028	1,114	$1,199 \\ 1,225$	1,285	1,341 1,371
95	262	350	437	525	612	700	788	875	963	1,050	1, 138	1,225	1,313	1,400
96	268 273	357 364	446 455	536 546	625 637	715 728	804 819	893 910	983 1,001	$1,072 \\ 1,092$	1,161	1,251 1,274	1,340 1,365	1, 429 1, 456
98	278	371	464	557	650	743	835	928	1,021	11.114	1,207	1, 300	1,392	1, 485
99	284	379	473	568	663	757	852	947	1,041	1,136	11.231	1,300 1,325	1,420	1,485 1,515
	200	386	482	579	675	772	869	965	1,062	1,158	1,255	1,351	1,448	1,544
101 102	295 301	393 401	492 502	590 602	688 702	787 803	885 903	983	1,082 1,104	1,180	1,278 $1,304$	1,377 1,405	1,475 1,505	1,573 1,605
103	307	409	512	614	716	819	921	1.023	11.126	$1,204 \\ 1,228$	1,330	1.433	1.535	1.637
104	313	417	522	626	730	835	939	11.1143	11. 14X	11.252	1,356	1,461 1,489	1,565 1,595	1,669 1,701
105	319	425	532	638	744 758	851	957	1,063		1,270	1,382	1,489	1,595	1,701
100	325 331	433 442	542 553	650 663		867 884	975	11.083	1, 192	1,300 $1,326$	1,408 1,437	1,517 1,547	1,625 1,658	1,733 1,768
108	337	450	563	675	773 788	900	995 1,013	1,105	1 238	1 350	1, 463	1 575	1 688	1,700
109	344	459	573	688	803	917	1,032	1,125 1,147	1,238 1,261	$1,350 \\ 1,376$	1, 491	1,575 1,605	1,688 1,720	1,800 1,835
101 102 103 104 105 106 107 108 109	350	467	583	700	817	933	1,050	1,167	1,283	1,400	1,517	1,633	1,750	1,867
111 112 113 114 115 116 117 118 119	356 362	475 483	594 604	713 725	832 846	951 967	1,069 1,087	1,188 1,208	1,307 1,329	1, 426 1, 450	1,545 1,571	$1,664 \\ 1,692$	1,782 1,812	1,901 1,933
113	369	492	615	738	861	984	1,107	1.230	1,353	1,476	1,571 1,599	1 722	1,845	l 1.968
114	375	501	626	751	876	1,001	1,126	1,252 1,273	1,377	1,502	1,627	1,752 1,783	1,877	2,003 2,037
116	382	509	637	764	891	1,019	11. 146	1,273	1,401	1.528	1,655	1,783	1,910	2,037
117	389 396	519 528	648 660	778 792	908 924	1,037 1,056	1,167	1,297 1,320	1,426 1,452	1,556 1,584	1,686	1,815	1,945 1,980	2,075
118	403	537	672	806	940	1,075	1,209	1,343	1.478	1.612	1,716 1,746	1.881	2,015	2,112 2,149
119	410	547	683	820	957	1,093	1,209 1,230	1,343 1,367	1,503	1,640	1,746 1,777	1,913	2,015 $2,050$	2, 107
120	417	55 6	695	834	973	1,112	1,251	1,390	1,529	1,668	1,807	1,946	2,085	2,224
		l	1	<u> </u>	!	l	1 .	1	<u> </u>	1	1	1 .	<u> L</u>	!

¹ Scale for logs 18 to 32 feet in length to be used only on National Forests in Alaska and on the West slope of the Cascade Mountains in Washington and Oregon, or as otherwise provided by specific instructions from the Forester.

 $\mathsf{Digitized} \ \mathsf{by} \ Google$

Ties may be sold by the piece, actually scaled, or counted and the number multiplied by the average contents, as the contract provides. The following ratios may be used:

Eight-foot ties, standard face, 33½ board feet each, may be used, or 30 ties to the thousand; 8-foot ties, second class, and 6-foot ties, standard face, 25 board feet each, or 40 ties to the thousand.

Shake and shingle-bolt material will be measured by the cord or by the thousand feet board measure, in accordance with local custom. As a rule, a cord of shingle bolts may be considered equal to 600 feet b. m.

Lagging may be measured by the cord or linear foot or by the piece, or where split lagging is used by the board foot, each cubic foot counting as 12 board feet.

Poles, posts, piles, converter poles, telephone poles, and stulls may be scaled, sold by the linear foot, or sold by the piece, as circumstances warrant.

When scaled, each stick of timbers, ties, posts, poles, or piles must be stamped on at least one end. Cordwood must be stamped at both top and bottom of each pile and at least 12 pieces in each cord must be stamped.

In check scaling as many logs as practicable will be scaled after they have been scaled by the officer in charge and without knowing his scale. The check will then be compared with the original scale. The log numbers of the original scale, as well as the length of logs, will in each case be recorded in the check scaler's book and the pages cut out and filed in the supervisor's office, or, when necessary, forwarded to the district forester through the supervisor, with the check scaler's report. Check-scale figures may be in the following form:


	Sound logs.			Unsound logs.			Totals.		
	Number of logs.	Scale.	Per cent + or	Number of logs.	Scale.	Per cent + or	Number of logs.	Scale.	Per cent + or
Scale									
Check scale									

Any feasible plan may be adopted by supervisors to permit the checking of the count or measurement of material other than saw timber.

Logs may be followed through the mill to determine how they "open up," but regular mill-scale studies as a check on the scale are rarely advisable, since there are too many variable factors which influence the mill output.

SALE OF MISCELLANEOUS FOREST PRODUCTS.

The sale of wild seedlings and Christmas trees, where the value is less than \$100, and such products as cascara bark and turpentine will ordinarily be conducted by the supervisor under directions from the Forester or district forester.



APPEALS.

All complaints and appeals arising from action taken by a Forest ranger or other subordinate officer on a National From decisions of Forest, either relating to applications for purchases of timber or to the enforcement of the terms of an existing contract, will be referred in the first instance to the supervisor for decision. Decision will be rendered by the supervisor in writing and a copy filed with the record in the case.

Appeals from the action taken by a supervisor must be filed with him within 15 days from the date of such action or from decisions of decision in the case of appeals arising under the enforcement of existing contracts and within 30 days in the case of appeals arising in connection with applications to purchase timber, or for the modification of an existing contract. The supervisor will transmit the appeal, with all supporting evidence submitted, to the district forester, together with the complete record in the case and his further recommendations and statement of the facts or reasons upon which his action was based. Decision will then be rendered by the district forester and the supervisor and appellant notified.

Appeals from decisions of a district forester or of the Forester will follow the same procedure and be governed by the same time limits. The district forester will transmit the appeal to the Forester, with all supporting evidence submitted, the complete record in the case, and his own recommendations and statement of the facts or reasons upon which his action was based. Similar data will be transmitted by the Forester to the Secretary in case of appeals from decisions of the Forester. Decisions rendered by the Forester will be transmitted through the district forester to the supervisor and appellant.

Decisions on appeals rendered by supervisors will be prepared in triplicate. The original will be sent to the appellant and the extra copy to the Forest officer concerned.

Decisions rendered by a district forester will be prepared in triplicate. The original will be sent to the appellant and the extra copy to the supervisor.

Decisions rendered by the Forester will be prepared in quadruplicate and by the Secretary in quintuplicate. The original will be sent to the appellant and copies furnished for the files of the Forester, district forester, and supervisor.

RECORDS AND REPORTS.

The Forest officer in charge will notify the supervisor when cutting begins on any advertised sale. The scale in all sales will be reported on Form 820 to the supervisor and a duplicate retained in the ranger's files. In unadvertised sales only the final report need be submitted. In advertised sales cutting reports will be submitted while work is in progress, covering periods of one, two, three, or four weeks, as may be required by the supervisor, but in each case ending with Saturday. On Forests where there are a number of sales in operation definite dates may be set upon which the cutting reports shall be submitted.

As cutting reports (Form 820) are received they will be compared with the timber sales record card for errors in entries brought forward from the last report and for the correctness of the rates. All calculations will be checked and the information regarding the progress of the sale closely scrutinized. The date of the report, quantity of each class of material cut reduced to feet board measure, according to approved converting factors, and total value of material cut since the last report and to date will be entered on the record card. The total value of the cut to date will be compared with the total deposits to guard against cutting in excess of payments.

Supervisors may in their discretion furnish approved cutting reports to purchasers on Form 820 without the answers to the questions on

the back.

In large sales a record of the scale of each log must be kept on file in the office of the supervisor in the book in which it was originally entered. It will be open to inspection by the purchaser at all times, but only in the presence

of the supervisor or an officer from the district office.

The monthly report on Form 949 will be mailed to the district forester by the supervisor not later than the 5th of the succeeding month, even if during the month no timber has been sold or cut. It will be compiled from all Forms 615, which will not be placed in the closed records until the end of the month. Timber cut in sales and in settlements in which payment is made will be included. The date of the approval of the agreement or stipulation will in each case be taken as the date of sale, even though advance cutting may have been allowed. The date of receipt of the cutting report will be taken as the date of cutting for the report; all data will be checked before the report is forwarded.

The report should include a statement of the amount of timber previously reported as sold which will not be cut owing to cancellations

or modifications of contracts during the month.

As soon as practicable after the 1st of each month the district forester will report to the Forester the amount and value of green and dead timber sold and cut, respectively, during the preceding month, by Forests. This report should include a statement of the amount of timber previously reported as sold which will not be cut owing to cancellations or modifications of contracts during the month.

The annual report will be compiled from the

Annual report. monthly reports.

Sales of miscellaneous forest products, such as Christmas trees, turpentine, seedlings, etc., should be reported in the form of a footnote to the district foresters' monthly and annual report of timber cut and sold.

Converting equivalents will be used in reducing various materials to feet board measure. Tables of converting factors will be prepared in each district to meet varying conditions. Before these are adopted they will be

approved by the Forester.

A summary (Form 616) of the timber business will be kept in the district office for each Forest and the card filed in front of all other record cards for the Forest. Each supervisor will keep Form 616 for his Forest. In order

that this form may show separately the amount of live and dead timber cut, supervisors will enter in red ink on this card form all the dead timber sold and cut and its value. Entries for live timber will be made in black ink. At the end of each month the quantity and value of each class of timber sold and cut will be entered on the summary card. At the end of each fiscal year the summaries by Forests will be totaled and entered upon a summary card for the district, which will be filed as the front card in the current record file. The timber cut in free and administrative use will be included in the total cut for the year.

The annual cost of timber sales for the fiscal year on each Forest will be considered with the amount of timber sold and cut, to determine whether the cost has been excessive.

Occasionally it may be necessary to secure detailed figures on representative large or small sales, showing the relation of the cost of sales

to the stumpage price received.

(Case designation.)

The following form should be used for reporting and recording timber sale costs. When advisable, in the judgment of the supervisor or district forester, mimeographed sheets may be prepared with ruled columns for periodic entry of the days and amounts chargeable to the various cost items, particularly to marking, scaling, and brush burning.

Examination:
 (a) Salaries of men (in cents per 1,000 feet or per cord). (b) Supplies, transportation, etc. (in cents per 1,000 feet or per cord). (c) Total cost of examination (in cents per 1,000 feet or per cord).
(b) Supplies, transportation, etc. (in cents per 1,000 feet or per cord).
(c) Total cost of examination (in cents per 1,000 feet or per cord).
Office work:
In local office (in cents per 1,000 feet or per cord).
Field work:
 (a) Marking (in cents per 1,000 feet or per cord). (b) Scaling (in cents per 1,000 feet or per cord). (c) Brush burning (in cents per 1,000 feet or per cord).
(b) Scaling (in cents per 1,000 feet or per cord).
(c) Brush burning (in cents per 1.000 feet or per cord).
(d) Check scaling (in cents per 1,000 feet or per cord).
Administration:
(a) Supervision (in cents per 1.000 feet or per cord).
(a) Supervision (in cents per 1,000 feet or per cord).(b) Total cost per 1,000 feet or per cord of administration.
(1) 2000 000 FOR 2,000 000 00 Walliam 000 Walliam 000 000 000 000 000 000 000 000 000 0
Area of sale

Area of sale							 	
Amount of timber of	eut		.				 . .	
Species			.				 	
Price							 . .	
		(Per cord	l or per	1,000 fee	t b. m., et	c.)		
Total cost of sale		(Per co	rd or pe	r 1,000 fe	et b. m.)		 • • • • • • •	
Remarks						· · · · · · ·	 	• • • • • • • •
							 	• • • • • • • •
· · · · · · · · · · · · · · · · · · ·							 	

(Reasons for high or low costs. If sale is not closed, what will be the probable cost? Are data approximate or exact?)

ADMINISTRATIVE USE OF TIMBER.

Timber may be disposed of under the administrative use regulation (Regulation S-17) by sale, under free use, or otherwise to remove an actual menace from insects, fire, disease, or other sources. Timber may be removed under this regulation when it is necessary for the construction, maintenance, or repair of permanent improvements upon National Forests or for experiments conducted by the Forest Service. Exchanges of timber for labor, services, or material in the building of permanent improvements are, however, not authorized.

Under this regulation the district foresters may authorize super-Authority of district foresters and amounts depending upon the conditions on the supervisors. Forest and the experience of the supervisor, within

the amount which each supervisor is authorized to sell.

When an application is received or the supervisor believes from personal knowledge or from the reports of Forest officers that timber should be disposed of under administrative use, he will direct a field examination and the preparation as soon as practicable of a map and a complete report in accordance with Forms 578a and 578b.

If it is found that because of disease, insect attack, or other cause a body of timber is a menace to the Forest, it will, if possible, be removed promptly with as little expense as possible, preferably by sale, and in such a manner as to reduce to a minimum the future danger. When a sale can not be made and regular free use will not remove the timber soon enough to prevent loss, administrative use permits will be issued.

Forester's administrative use permits will be prepared in quintuplicate, and district forester's in quadruplicate. The permits will be executed in duplicate, and the executed copies forwarded to the Forester or district forester, as the case may be, for approval with the report and recommendations of the supervisor. The approved original will be filed in the district office, the duplicate transmitted to the permittee and copies furnished the supervisor and local officer in charge. The fifth copy, in Forester's permits, will be retained in the Forester's files.

The card record on Form 615 in the supervisor's office will be kept as an index card and record of the amounts cut as in sales.

The permit will be prepared in triplicate. The original is for the permittee, the duplicate for the supervisor's files, and the triplicate for the ranger.

Form of permit. In preparing the permit the following form will serve as a guide:

ADMINISTR	ATIVE	USE	PERMIT.
-----------	-------	-----	---------

(Date of application.) National Forest. (I or we)
(If copartnership, give names and addresses of individuals, followed by "partners doing business under
the firm name and style of ;" if corporation, "A corporation organized and existing under the
laws of the State (or Territory) of , having an office and principal place of business at
, hereby apply for permission to take, within months from above
date, all
marked or designated for cutting by the Forest officer, the removal of which is actually necessary to protect the forest from ravages or destruction, located on an area to be
definitely designated by the Forest officer before cutting begins in(Give approximate
location and describe by relation to some well-known landmark, stream, etc. Give also legal subdivision
if surveyed and approximate legal subdivision if unsurveyed.)
estimated to be
If this application is approved agree, in consideration of the granting (I or we)
of the privilege herein applied for, to cut and remove said timber in strict accordance with the following and all other regulations and instructions governing National Forests prescribed by the Secretary of Agriculture.
(Insert regulations to govern cutting and removal of the timber.)
Signed in duplicate this day of, 19
Witnesses:
(Signature.)
Approved at, under the above conditions,
(Signature of approving officer.)
(Title.)
70 1 101 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1

Bonds will be required only in exceptional cases when necessary Bond, when re- to insure faithful compliance with the conditions of the permit.

Forest officers will designate cutting areas and mark the timber to be removed as in timber sales. All administrative use of timber except that cut or used for permanent improvements on the National Forests will be scaled, counted or measured, and stamped.

5276°--11----5

The ranger will file his copy of the permit alphabetically by name of the permittee. When the case is closed or the permittee mittee is notified that the cutting area is in a satisfactory condition, the date of closing or notice and the amount and value of material secured will be entered on the back of the permit.

Timber cut under administrative use except that cut or used in connection with permanent improvements on the National Forests will be included in the ranger's annual

free-use reports to the supervisor.

As soon as the conditions of the permit have been complied with, the permittee will be notified by the supervisor that the cutting area is in a satisfactory condition and the administrative use closed.

TIMBER SETTLEMENT.

Settlement for timber cut, damaged, killed, or destroyed on the National Forests in connection with the enjoyment of any special-use

privilege is called a timber settlement.

Where the timber will be killed or destroyed but not removed, or in those cases where it will not be worked into measurable or able form, or where the cutting is done in such a way that scaling is impracticable, settlement may be required on the basis of estimate. In all cases where the timber can be scaled, measured, or counted, it will be paid for according to the scale, measure, or count, as in a timber sale, and the procedure will be identical.

A charge for timber settlements on the basis of current stumpage rates for timber of like quality and accessibility included in sales will be made for all classes of material which have to be cut and destroyed and which are commonly salable upon the Forest. A charge will not be made for classes of material which are not commonly salable on the Forest, or, ordinarily, for reproduction. The basis for this procedure is that the ground rental under the occupancy permit covers the probable future returns from timber growth; or when no rental is charged that the land is being put to a higher use and the people as a whole are benefited more than if it had been retained in the production of timber.

When a right of way permitted under an act of Congress crosses an unpatented agricultural or mining claim, whether the claim antedates the right of way or not, and whether the claim is apparently held in good faith or not, if timber is cut and removed in clearing the right of way, payment will be made to the United States in all cases except where the removal of the timber is necessary for the purpose of clearing the land in good faith for cultivation or for development, or when at the time of cutting the timber is actually needed by the claimant for use in making improvements on the land embraced in his entry or location. If any such claimant should need timber for the purposes above specified and should be unable to obtain it on his claim, he will be allowed to take timber under free-use permit from lands of the United States for those purposes up to the amount cut from the claim for which the United States has received payment. It is therefore necessary to keep separate records of the timber estimated upon or cut from each claim.

When timber is involved in a special-use case, the Forest officer making the examination will report on the timber to be cut, damaged, killed, or destroyed, giving the information called for by Form 578a and an estimate of the timber on Form 578b. In addition to the usual recommendations in timber sales, this report will contain recommendations as to whether

the timber should be paid for on the basis of the estimate or actual scale, and state when cutting or destruction is likely to take place.

Upon the receipt of these papers, the supervisor will record the case as in "Unadvertised Sales," using a white card (Form 615) stamped "Timber Settlement," which will be filed with the Timber Sale cards.

Special clauses covering payment for timber cut or destroyed in connection with occupancy permits and the disposition of refuse are included in the various forms or Timber settlement stipulations as follows:

Form 832, special-use permit, clauses 5 and 9. Form 80, railroad stipulations, clauses 1 and 2.

Form 81, stipulations in connection with irrigation, municipal, and mining easements, clauses 1 and 2.

Form 59, preliminary water-power permit, clause 6.

Form 61, water-power stipulation, clauses 23, 24, 26, and 27. Form 63, transmission-line permit, clauses 4 and 6.

Such modifications should be made in these clauses as are necessary

to adapt them to the particular conditions in each case.

The following clause should be inserted in stipulations or permits involving the use of drivable streams, when practicable and necessary to protect the interests of the Government in future timber sales:

To maintain suitable gates in the dam to provide for the driving of timber down the River or stream at such times as, in the judgment of the Forest officer, will not cause undue interference with the operation of the plant.

Deposits will be required in advance of cutting or Deposits. destruction.

Letters of transmittal and cutting reports, if payment is made upon the actual scale, will be handled as in timber sales. Cutting reports. In cases in which settlement is made on the basis of an estimate, one cutting report stating the total estimated amount cut or destroyed will be submitted upon completion of the work.

If the timber is cut, utilization as complete as in Utilization. current timber sales will be required.

Timber in settlements will be included in reports How reported. of timber "sold" and "cut."

Timber settlements will be closed when cutting is finished and brush properly disposed of, or if no timber is cut, Closing. when construction work is completed, independently of special-use permits or rights-of-way stipulations. If timber is damaged or destroyed subsequent to the closing of the timber settlement, the case may be reopened.

If the amount of timber involved in a special-use permit is more than the supervisor is authorized to approve in a When referred to district forester. sale, the case will be referred to the district forester with the report on Forms 578a and 578b and drafts

of timber settlement clauses to be included in the permit.

The supervisor's report and the drafts of clauses in every special use or Interior Department right of way which involves a timber settlement will be scrutinized with reference to payments, prices, and policy. The approved draft of the clauses and a letter of instructions will be sent to the supervisor in connection with the action taken upon the special use.

FREE USE OF TIMBER AND STONE.

As provided for on page 13, the supervisor of each Forest annually on April 1 will recommend to the district forester the maximum amount of timber which may properly be cut under free use during the ensuing fiscal year, which amount shall form a part of the maximum cut for the Forest. The free use maximum shall be based upon silvicultural conditions, the provisions of the working plan if one has been prepared, the amounts which have been cut under free use during past years, and the probable amount which will be needed during the ensuing year and which may be cut under the existing policy. The procedure in the district office will follow that outlined on page 14.

The free use of timber and stone on National Forests may be granted to bona fide settlers, miners, residents, and prospectors for minerals, for firewood, fencing, building, mining, prospecting, and other

domestic purposes.

The object of free use is to assist prospectors in their work and to encourage and assist settlers who have not on their own land or claims, or on lands controlled by them, a sufficient and accessible supply of material suitable for the purposes named in the law.

Whether an applicant is entitled to free use must be decided by the proper Forest officer. In all cases not clearly covered by the letter of the law and the regulations he will be To whom granted or refused. guided by their spirit, especially as indicated by the expression "Those who may not reasonably be required to purchase," and by the distinction between public or personal and commercial use. A member of a corporation is not necessarily debarred from free use of fuel for his own home, although his ability to secure it from another source will be considered, especially if the Forest supply is limited and in demand by more needy applicants. Residents of towns and villages engaged in business or earning a livelihood are reasonably expected to purchase building material for town dwellings and other home structures, and, except in small villages, for fuel. particularly under the Forest homestead act, who have not yet improved their homes, may receive a liberal allowance for their own use. There is no more reason for giving a hotel keeper or merchant timber solely to build or warm his hotel or store than giving him a stock of goods, yet it need not be refused the proprietor of a small establishment when it will be used chiefly by himself and his family. Prospectors may be assisted to develop their properties, but owners of producing mines and those who are able to employ several or many men on wages will be required to pay. Well-to-do stockmen and owners of large ranches may reasonably be required to purchase.

Free use of timber may be allowed in connection with other uses of the National Forests regardless of the ability of the permittee to purchase; if the timber will be used in improvements the benefit of which will be essentially public rather than individual, or if the stumpage value of the timber used is less than the value of these improvements for protective purposes, or for administrative purposes considering both the actual use of the improvement and the increased value of the Forest through better regulation. Ordinarily, improvements under these provisions should be constructed with the understanding that they will become the property of the United States at the termination of the permit. A clear line can usually be drawn between improvements which are necessary and of benefit only to the permittee in conducting his business and those which result in the improvement and better regulation of the Forest.

Free use may be refused in the discretion of the supervisor to permittees who repeatedly violate the provisions of their permits and interfere with the efficiency of the free use administration. Free use may reasonably be refused where the final cost to the permittees is as great as if the material were purchased, whether or not agents are employed to obtain the material. Free use of timber from alleged invalid claims may be granted for fuel only, pending the final deter-

mination of title to the claims.

Valuation of material will not be less than for sales in the same locality on the Forest

from which the timber is to be taken.

Supervisors will issue at the beginning of each fiscal year a schedule of standard rates for free use material based upon the current timber sale rates. The rate for the same class of material may be varied in different districts if the conditions warrant. In general, posts will be valued at a specified rate per post, and poles at a specified rate per linear foot. Cordwood will never be measured on the basis of board feet. Dead timber will be valued at the same price as green in National Forests where the prices are equal in sales.

The free-use privilege will be restricted so far as possible to diseased, defective, dying, and dead and down timber, the use of which will be encouraged. Green timber, however, may be obtained except as provided for in the regulations or the supervisor's instructions, when it is necessary for the particular needs of the applicant. Every possible attempt will be made to improve and protect the Forest by locating free use where the timber can best be spared or where it constitutes a menace, by confining the cutting in green timber so far as possible to inferior trees and inferior species, and where necessary or advisable for economic reasons or to insure reproduction by limiting the cut of green timber or prohibiting it altogether.

The duration of permits, which will not exceed the time necessary to remove material, will be fixed by the issuing officer, but all permits

must terminate on or before June 30 of each year.

The small amount of material actually needed by transients may be taken without a permit. In cases of great emergency use.

Transients and emergency material may be taken without a permit, but the fact should at once be reported to a Forest officer with the request that a permit be issued.

The administration of free use will be conducted mainly by the supervisors and rangers, subject to the general policy, restrictions, and instructions herein outlined, or prescribed by the district forester. It is the duty of Forest officers to cheerfully furnish assistance to applicants, to act promptly upon all applications, and in general to follow as liberal a policy in the matter of free use as the interests of the National Forest and the proper performance of their work will allow. Although simple methods and the exercise of judgment are encouraged, there should be no tendency to underrate the importance of the free-use business.

Every effort will be made to improve the Forest and to reduce the cost of the administration of free use and yet give Forest users prompt attention. Utilization of all trees cut, as complete as in sales, as well as careful disposal of refuse, must be required. Officers in charge of cutting will be held responsible for seeing that no unnecessary damage is done to reproduction, young growth, or standing timber. There should be no failure on the part of the Forest officer to make all points

clear to applicants before permits are granted.

When numerous applications for free use are expected, Forest officers will notify the public, in any convenient manner, that they will be at designated places on certain days, prepared to transact free

use and other National Forest business.

Wherever possible the work of handling the free-use business will be reduced by designating temporary permit areas, preferably in dead timber. These will be mapped and reported to the supervisor, who, if he approves, will authorize the ranger to mark or specify the timber which should be removed and to designate the boundaries. Great care should be exercised in establishing such areas, and their boundaries must be clearly designated. After issuing a permit, the Forest officer may send the permittee to this area, thus avoiding the necessity of a visit to the timber with each applicant before cutting. Each applicant, who will be held responsible for his cutting on the area, will be required to clear up the débris resulting from his own cutting.

Forest officers will designate the timber to be cut in the simplest and most economical way practicable. Living timber will be marked in accordance with the principles outlined under timber sales, and the detailed instructions for marking issued by the district forester or supervisor. In the case of dead timber, an area may be blazed or defined by natural boundaries, and

the class of trees to be taken specified.

The scaling or measuring of free-use material may be omitted when it would require long special trips or engage considerable of the ranger's time that could be more economically employed on other work. A sufficient check should be maintained by the ranger to be certain that the regulations governing

free use are complied with.

Supervisors and deputy supervisors will investigate the conduct of free-use business, both in the field and in the ranger's records, as often as possible, to see that the cutting is in accordance with silvicultural requirements, that utilization is complete, that the public is properly served, that the cases are closed promptly on expiration, and that the free-use policy for the Forest is being followed.

Cutting reports will be required by supervisors only when they consider them necessary in large permits to check the rate of cutting and the amount as against that fixed in the permit.

Rangers' free-use permits will be issued in duplicate on Form 874-8.

The approved original will be transmitted to the permittee and the ranger will retain the duplicate copy, which will be filed alphabetically by the name of the permittee in a promise card box. For convenience in closing, all permits will be made to expire at the end of a month. When a case is closed the date of closing and the amount and value of material secured will

be entered on the back of the permit.

If Form 874-8 is used in supervisors' or district foresters' permits the original will be sent to the permittee and a carbon filed by the ranger with other permits. If a special form is necessary which can not be conveniently filed with the Form 874-8 permits an index card will be used and the permit filed with timber sales. Rangers will recommend the closing of supervisors' and district foresters' permits and immediately close the case in their own files. No record of rangers' permits will be kept in the supervisors' offices.

Supervisors' permits will be prepared in triplicate on Form 874-8, or on a special form similar to Form 202 when necessary. The approved original will be transmitted to the permittee. The supervisor will retain the duplicate and forward the triplicate to the ranger. Supervisors may

require reports in large or unusual cases.

When an application exceeds the supervisor's authorization, he will prepare a permit in triplicate, which, with the necessary report and recommendations, will be forwarded to the district forester in duplicate for approval. After approval the permit and report will be returned to the supervisor, who will transmit the original to the permittee, one copy to the ranger, and retain one copy. No record of individual cases will be kept in the district office.

Whenever application is made for free use of timber to an amount exceeding the authorization of the district forester the application must be submitted to the Secretary of Agriculture for approval if the value exceeds \$500, and to the Forester if within this amount and above the authorization of the district forester. When so approved the district forester will issue the permit following the procedure outlined under "District

forester's permits."

At the end of each fiscal year, or at other times if required by the supervisor, each ranger will submit a report giving separately for live and dead timber the number of permits issued and the quantity and value of material actually used by the permittees. This report will cover all free-use and administrative-use permits, including those approved by supervisors and district foresters. Such reports will be incorporated in the supervisor's annual statistical report to the district forester.

Temporary free-use areas from which only dead fuel or dead fence material, or both, may be taken prior to securing a permit will be recommended by supervisors and approved by district foresters only where it is evident

that there will be substantial compliance with the law, where danger will not result, and where the elimination of routine will result in a material reduction in the cost of administration.

Free-use areas will preferably include large quantities of dead timber and will be closed as soon as the supply is exhausted.

Forest officers will see that the utilization on free-use areas is reasonably complete.

The cutting of timber by other persons or for other purposes than those named in the law or for sale is forbidden.

TIMBER SALE AND FREE-USE FORMS.

Form 941. (Revised Dec. 1, 1911.)		
UNI	TED STATES DEPARTMENT OF AGRICULTURE,	
(Attach clipping of noti	FOREST SERVICE-	
	BID FOR ADVERTISED TIMBER.	•
		10
	Mi-1 0-1-	, 19
•••••		
(The district fores	ter or Forest supervisor)	
(Cit	y or town)	
	(State)	
DEAR SIR: In res	sponse to the notice of sale published in(Name of n	ewspaper)
of(Town)	,	oid for the
timber advertised t	o be cut from(Locality)	
	subdivisions; if unsurveyed, give metes and bounds with referenknown landmark)	
Estimated amount in feet board measure, cords, or pieces.	Species. (If different prices are offered for dead and living timber, make separate entries.)	Price bid per 1,000 feet, cord, or piece.
I have remitted, (U. S. depository) notice of sale. Very truly ye	under separate cover, to theNational Bank \$, to accompany this bid, as required by the	of ne published
tory ordry y	(Name of bidder)	
	(Full address)	••••••



Form 202. Revised Oct. 15, 1911.)

UNITED STATES DEPARTMENT OF AGRICULTURE FOREST SERVICE

TIMBER SALE.

(Date of app	plication)	National Forest.
(I or we)	(If copartnership, "We,	and
partners, doing b	ousiness under the firm name and style of	'') (If corporation, "A corpo-
ration organized	and existing under the laws of the State (or Terri	tory) of , having an
office and princip	pal place of business at	")
of,	State of, hereby(In application,	"apply," in final agreement, "agree.")
• • • • • • • • • • • • • • • • • • • •	to purchase	(In final agreement only, "In
accordance with	my (or our) bid submitted in pursuance of the not	ice of sale of certain timber in the
Nation	al Forest, duly given by publication as required b	y law," if sale has been advertised and
bid accepted. If	private sale, when timber has been advertised and	d no satisfactory bid has been received,
"at private sale,	certain timber within the N	ational Forest , duly
advertised for sale		al circulation in the State (or Territory)
in which said For	rest exists, by notice published for not less than 30	days before , 19 . Said timber
is") all the mercha	antable dead timber standing or down an	d all the live timber
("Marked" or "		st officer located on an area of
	eres to be definitely designated by a	
begins in	Give approximate location and describe by rel	ation to some well-known landmark,
	ve also legal subdivisions, if surveyed, and approx	
If advertised, des	scription of location should follow that given in no	tice of sale.)
• • • • • • • • • • • • • • • • • • • •	within the	National
Forest, estima	(Give by species the quantity in prop	er unit of measure, state whether live
or dead, and kind	d of material, and add the words "more or less.")	
("If this sale is av	warded to me (or us)" in application only.) (I or	we.)
do hereby, in	consideration of the sale of this timber t	(Me or 118.)

74 NATIONAL FOREST MANUAL—SALE AND FREE-USE FORMS.

to ti	he
plac	red to the credit of the United States,
dolla	rs (\$), more or less, as may be determined by the actual scale, measure, or count.")
for t	he timber at the rate of
• • •	(Per thousand feet b. m., cord, linear feet, etc.)
in a	dvance payments of at least dollars (\$) each when called for by
the	Forest officer in charge
State	s depository at this time to cover cost of advertising, this amount to be placed to my (or our) credit if
I am	(or we are) the successful bidder, or refunded if my (or our) bid is rejected.")
cred Stat	it being given for the sums, if any, heretofore deposited with the said United es depository or officer in connection with this sale.
accordance of the second secon	nd further promise and agree to cut and remove said timber in strict (I or we.) with the following conditions and all regulations governing timber sales cribed by the Secretary of Agriculture: Timber upon valid claims and all timber to which there exists valid claim under stact with the Forest Service is exempted from this sale. No timber will be cut or removed until it has been paid for. No timber will be removed until it has been scaled, measured, or counted by a set officer. No timber will be cut except from the area specified by a Forest officer. No timber will be cut except that marked or otherwise designated by a Forest
offic 5. road 6.	
trees the will	no trees shall be left lodged in the process of felling. (Unmarked or undesignated.) Is that are badly damaged during the process of logging will be cut if required by Forest officers, and when such damage is due to carelessness, the trees so injured be paid for at twice the price herein specified. The approximate minimum diameter limit at a point 4½ feet from the ground to
whic	ch living trees are to be cut is
trees	are marked for cutting, "Trees above these diameters may be reserved for seed or protection, and
merc	hantable trees below these diameters may be marked at the discretion of the Forest officer." When
other	methods of cutting are advisable, insert suitable provisions so that the system of cutting and method
of de	signation will be clear.)
9.	Stumps will be cut so as to cause the least possible waste and will not be cut

higher than inches on the side adjacent to the highest ground—lower when possible—except in unusual cases when, in the discretion of the Forest officer, this height is not considered practicable.

10. All trees will be utilized to as low a diameter in the tops as possible so as to cause the least waste, and to a minimum diameter of inches when merchantable in

the judgment of the Forest officer; the log lengths will be varied so as to make this possible.
11. Tops will be lopped and all brush piled compactly at a safe distance from living trees, or otherwise disposed of, as directed by the Forest officer. 12. All timber will be cut and removed on or before and none later than
, and at least will be paid for, cut, and removed (Feet b. m., cords, etc.)
on or before
required by the Forest officer, will be piled or skidded for scaling
"count" if cordwood or other material is involved.) 14. All marked or designated trees and all dead timber sound enough for lumber of
any merchantable grade or timbers
completed, or is not removed from the National Forest after the expiration of this agreement, shall be scaled, measured, or counted, and paid for at double the price herein specified.
15. During the time that this agreement remains in force will, inde-
pendently, do all in
which
property or the area embraced in this agreement shall be paid for serv-
ices so rendered at the rate or rates to be determined by the Forest officer in charge, which rate or rates shall correspond to the rate or rates of pay prevailing in the
the services are rendered, provided, however, that if
responsible for the origin of the fire, shall not be paid for services so rendered. (I or we.)
16. So far as is reasonable, all branches of the logging shall keep pace with one another, and in no instance shall the brush disposal be allowed to fall behind the cutting, except when the depth of the snow or other adequate reason makes proper disposal impossible, when the disposal of brush may, with the written consent of the Forest officer in charge, be postponed until conditions are more favorable. 17. Necessary logging roads, chutes, camps, buildings or other structures shall be located as agreed upon with the Forest officer in charge. All such improvements not removed withinmonths after the expiration of this agreement shall become the property of the United States.
(Insert special conditions, if any.)
The title to the timber included in this agreement shall remain in the United States until it has been paid for and scaled, measured, or counted, as herein provided.

The decision of the Secretary of Agriculture shall be final in the interpretation of the regulations and provisions governing the sale, cutting, and removal of the timber

covered by this agreement.

Work may be suspended by the Forest officer in charge if the conditions and requirements contained in this agreement are disregarded, and the failure to comply with any one of said conditions and requirements, if persisted in, will be sufficient cause for the Forester to revoke this agreement and to cancel all permits for other uses of the National

No Member of or Delegate to Congress, or Resident Commissioner, after his election or appointment, and either before or after he has qualified, and during his continuance in office, shall be admitted to any share or part of this contract or agreement, or to any benefit to arise thereupon. Nothing, however, herein contained shall be construed to extend to any incorporated company, where such contract or agreement is made for the general benefit of such incorporation or company. (Section 3741, Revised Statutes, and sections 114 to 116, Act of March 4, 1909.)

Refund of deposits under this agreement will be made only at the discretion of the

Forester or district forester.

This agreement will not be assigned in whole or in part.

The conditions of the sale are completely set forth in this agreement, and none of its terms can be varied or modified except with the written consent of the Forester.

(or, "the district forester" in district forester's sales, or, "the supervisor" in supervisor's sales.) No other Forest officer has been or will be given authority for this purpose. And as a further guarantee of a faithful performance of the conditions of this agree
ment
singular the conditions and requirements herein set forth, or made a part hereo be retained by the United States to be applied as far as may be to the satisfaction
of obligations assumed hereunder.
Signed in duplicate this
(Corporate seal if corporation.)
Witnesses: 1
(Signature of purchaser. See note.)
(Signature of purchaser.)
Approved at, under the above conditions,, 191
(Signature of approving officer.)
(Title.)
Note.—If contracting party is a copartnership, form of signature should be X Y Z COMPANY, By John Doe, A member of the firm.
If contracting party is a corporation, form of signature should be
(X Y Z COMPANY,
By John Doe, President (or other officer or agent).

¹ Signature of two witnesses required if sale is over \$100.

Form 377. (Revised Dec. 1, 1911.)

UNITED STATES DEPARTMENT OF AGRICULTURE.

FOREST SERVICE.

BOND,

KNOW ALL MEN BY THESE PRESENTS: That we(Names of principals.)
of .
on principal and
as principal, and
suret, are held and firmly bound unto the United States of America in the sum of dollars (\$), for the payment of which sum well and truly to be made to
the
(Names of principals.)
ha. by a certain
Now, Therefore, If the said(Names of principals.)
1.11
shall well and truly perform all and singular the promises and agreements in said
In Witness Whereof, The parties hereto have executed this instrument this
day of, 19., at
(Surety.)
ACKNOWLEDGMENT OF PRINCIPAL.
STATE OF, COUNTY OF, 88:
On thisday of, 19, before me(Name of notary.)
, a notary public, in and for, residing therein, duly
sworn and acting under a commission expiring, 19, personally appeared
(Name of principals)
(Name of principals.) known to me to be the

(Name of purchasing company.) the corporation that executed the above instrument, and known to me to be the person
who executed the above instrument in behalf of the said corporation, and acknowledged to me that he said corporation executed the above instrument, as principal, voluntarily for the uses therein specified. Witness my hand and official seal the date first in this certificate above written.
[SEAL.]
Notary Public. N. B.—Italics are to be stricken out when bond is executed by individuals and not by corporations.

 $\mathsf{Digitized}\,\mathsf{by}\,Google$

ACKNOWLEDGMENT OF SURETIES.

STATE OF, COUNTY OF	, 88:
On this, 19.	., before me(Name of notary.)
, a notary public, in and	for, residing therein, duly
	expiring, 19, personally appeared
(No	ame of sureties.)
known to me to be the(Title	of the
(Name	of surety company.)
who executed the above instrumer acknowledged to me that he said corrily for the uses therein specified. WITNESS my hand and official seal	instrument, and known to me to be the person at in behalf of the said corporation, and each poration executed the same as surety, voluntathe date first in this certificate above written.
[SEAL.]	Notary Public.
N. B.—Italics are to be stricken out when bo	and is executed by individuals and not by corporations.
TAO	OF SURETIES.
[Must be used w	hen individuals are sureties.]
STATE OF, COUNTY OF	
being duly sworn, each for himself say resident of	and(Name of surety.) s that he is a citizen of the United States and a that he signed the above bond
as one of the sureties thereon; that he	is worth the sum ofin property in the
of his residence over and	above all legal liabilities and exemptions, and
that he has property therein subject t	o sale on excution worth the sum of
	(Surety.)
	(Surety.)
Subscribed in my presence b	yand (Name of surety.)
(Name of surety.)	, and by each of them sworn to before me
thisday of, 19	
WITNESS my hand and official seal	the date last above written.
[SEAL.] Notary Public in and My commission expires	for the County ofState of
	ATE OF SOLVENCY.
I hereby certify that I have made d	hen sureties are individuals.] ue and diligent personal inquiry as to the ability nd am satisfied that they are good and sufficient ofdollars.
	(Title.)
	• • •
Approved at(City.)	,, 19 (State.) (Date.)
•	(Signature of approving officer.)
* * * * *	(Title.)

Form 319. (Revised August, 1908.)

UNITED STATES DEPARTMENT OF AGRICULTURE,

FOREST SERVICE.

MEMORANDUM OF CORPORATE OFFICER'S AUTHORITY TO SIGN INSTRUMENT.

When an agreement or other legal instrument is executed by a corporation, the Forester requires evidence of the authority of the person who signs on behalf of the corporation. Such evidence should be EITHER— (1) A copy of the article of incorporation, or of the by-law giving the requisite authority, or (2) A copy of the resolution of the board of directors giving the requisite authority. In either case SUCH COPY SHOULD BE FOLLOWED BY a certification by the secretary of the company, under the corporate seal; the evidence of authority required would then be substantially in the following form:
(Copy of article of incorporation, by-law, or resolution.)
······
I,, secretary of the
powers of the
in full force and effect; and that on said date
was the
In witness whereof I have hereunto subscribed my name as secretary of the
pany this day of, 19
[CORPORATE SEAL.]
Secretary of the
5276°—11——6

(Space for name on right-hand margin to be filled in before filling. Amount out and	
value to be inied in on closing.)	[REVERSE.] (Space at bottom to be filled in by officer closing the case, on retained duplicate.)
Form 874-8.—Revised Dec. 1, 1911.	
U.S. DEPARTMENT OF AGRICULTURE,	·
FOREST SERVICE.	
FREE-USE PERMIT.	In consideration of such permission said permittee agrees to—
National Forest,	1. Cut only such timber as is designated by a Forest officer.
Permission is hereby granted to	2. Remove no timber until permission is given.
(Name of permittee.) of	3. Conduct the cutting and dispose of the refuse as directed by the Forest officer.
to take, within months from	4. Neither sell, give away, nor exchange any material taken.
above date, from(Describe lands.)	5. Assist Forest officers to fight fire during the period of this permit
	without pay if the area covered by this permit is on fire or threatened; otherwise at the prevailing rate of
the following-described timber:	pay.
(Specify species and state whether	6. Comply with all other regula- tions governing National Forests.
dead or living; number of cords and	Permit granted under above conditions.
value per cord; number of feet b. m.	
and value per thousand; number and	
dimensions of house logs, posts, or	
other special products, and rate of	(Title.)
valuation.)	
alue,	The cutting or taking of any timber under this permit makes all the
worth \$, to be used	conditions binding.
by said permittee(How and where.)	
!	(Date closed.)

	Page.
Administration of free use	69
sales, general	44
compliance with contract	45
large sales	45
small sales	44
subordinates of purchaser	45
when cutting may begin	45
	62
Administrative use	
authority of district foresters and supervisors	62
bond, when required	63
card records	62
closing	64
field examination	62
methods of disposal under	62
permits, Forester's and district forester's	62
form of	63
ranger's record of	64
supervisors	62
	62
purpose of	
regulation	10
report of timber cut	64
supervision of cutting	63
Advance cutting, applications discouraged	25
district forester's and Forester's sales	19
form of application	26
limitation in amount	27
procedure	26
procedure provision to be made for other bidders	27
provision to be made for other bidders	
regulation	. 8
supervisor's advertised sales	17
Advertisement, authority to publish	22
classification of sales by	14
correcting mistakes in	21
date for receiving bidsessential features to be covered in	21
essential features to be covered in	20
form of	21
general notice	22
location of timber	20
papers in which published	20
period, minimum	20
nublicity in addition to	23 23
publicity in addition toreport of, in district forester's and Forester's sales	
report of, in district forester's and Forester's sales	19
in supervisor's salesrequired in sales exceeding \$100 in value	17
required in sales exceeding \$100 in value	8, 16
sale of part of timber advertised	22
Alaska, exportation of timber from National Forests in	9
free use on national forests in	12
special scaling rule for	51
special scaling rule fortimber cutting on right of way or in connection with a special use	11
Allotments at highest price bid to prevent monopoly	9
Annual cut. See Limitation of annual cut.	
Appeals	10, 59
from decision of representations	59
from decision of ranger	
from decision of supervisor	59
from decision of district forester	59
from decision of Forester	59
record	59

	rage.
Applicants, explanation and demonstration to, of sale requirements	42
reliability and financial standing of	42
Application, actual purchaser required to make	42
advance cutting	26
advance cutting	18
district forester's sales	18
Forester's sales.	20
preparation of	36
special clauses for	43
supervisor's advertised sales.	16
	42
to follow terms of contract	
Appraisal of timber	7
free-use material.	68
Area. See Cutting area.	aa =a
Areas, free use	, 69, 70
Awards. See Bids and awards.	_
Ax, regulation marking	9
Bids and awards	23
award of sale	23
date for receiving bids	21
deposits accompanying bids	23
district forester's and Forester's sales	19
refunds to unsuccessful bidders	23
supervisor's sales. Black Hills National Forest, prohibition against exportation from	17
Black Hills National Forest, prohibition against exportation from	9
Blue sap	55
Bonds, advance cutting, regulation	9
amount, how determined	25
district forester's and Forester's sales	
evidence of authority of person signing	25
examination of, periodically	25
form	95 77
formincreased if brush piling postponed	20, 11
merceased in brush prining postponed.	0.10
regulation	9, 10 17
supervisor's advertised sales	
sureties	25
when required, timber sales 9	
administrative use	63
Brush disposal	48
burning as cutting progresses	49
burning piles	49
detailed instructions	50
ground burning	49
insect-infested or fungus-infected trees	49
piling	48
postponement of piling	33, 49
bond to be increased	33
form of application	33
rate of	50
scattering	49
time for burning	49
Brush piling. See Brush disposal.	
Burning brush. See Brush disposal.	
Cabins, use of timber in construction of	10
Camps and improvements	40
Camps and improvements	-0
Card record. See Records and reports.	
Cascara bark, sale of	58
Cat face	54
Center rot, uniform	53
Check marking. See Marking.	00
on total number of logs in skidways	50
Cheeke door	55 55
Checks, deep	
deep spiral	55 50
Christmas trees, sale of	58
	11 10
Churches, free use to	11, 12

	T WEG.
Circular rot, uniform	53
Circular shake	54
Claims. See also Mining locations.	
alleged invalid, free use of timber from	68
payment for timber cut onunperfected, cutting timber on	39, 65
unperfected, cutting timber on	9, 39
Clean cutting. See Marking.	
Closing, administrative use	64
ranger's sales	15
supervisor's sales	17
timber settlement cases	66
Conditions of sale	9
removed denned	36
time limits	36
	30
Contractsform for	31, 33 23
cancellation	23 34
enforced	35
field examination before	35
form for advertised sales	34
execution to be promptly made	23
district forester's and Forester's sales.	10 20
avidance of suthority person signing	24
evidence of authority, person signing	24
form	
modification, general	8, 30
approval	34
bond increased if brush piling postponed	33
conditions under which allowed	30
consent of surety to be obtained	30
consent of surety when brush piling postponed	33
evidence of authority of person executing	30
extension of time	32
extensions exceeding five years	
extensions of time, form of application	33 30
form	
postponement of brush piling	33
payments not allowed	30
ranger's sales	15 34
record of, how kept	
verbal, prohibitedwhen extension refused—disposal of timber	30 33
when extension refused—disposal of timber	33 15
ranger's salessample, in district forester's and Forester's sales	10 00
spanial alarmos	10, 20
special clausessupervisor's advertised sales	43
when submitted to successful bidders.	17 23
witnesses to the execution of	23 24
Converting factors, use of, in preparing reports	60
Cooperative organizations of settlers, free use to	11 19
Cost data	61
Cost data	61
Costs, logging and milling, data on, in proposed sales	42
Counting. See Scaling.	72
Crotches	56
Curve or sweep	55
Cutting area, how designated	38
Cutting methods to be determined before sale begins.	37
Cutting period. See Time limits.	٠.
Cutting reports. See also Timber sales.	
check and record of	60
free use cases	70
timber settlement cases	66
Dead timber, to be included in all sales.	37
Defects in logs. See Scaling.	٥,
Departments, free use to other	11
Coorle	
Digitized by Google	_

		Page.
	ayments, and Letters of transmittal.	0.00
	•••••••	8, 28 29
when mad	le in timber settlement cases	66
	est description.	00
Designating timber for	or cutting. See Marking.	
Destruction, disposal	of timber to prevent	10
Diameter limits, appr	oximate, basis for determining	3
,	to be flexible	47
	when necessary	37
Diameters, finding, in	n scaling	5
Diseased timber, disp	oosal of, under free use	68
701111111111111111111111111111111111111	under administrative use	63
District forester's sale	s. See Timber sales.	4.
District marking boar	d	40
Emergency sales. Se	a Advance cutting	5
Emergency sales. De	of, on National Forests	10
Estimate in proposed	sales. See Examination of timber.	
Evidence of authority	y to execute contract, bond, etc	2
Bylaches of maniers,	modifications	3
Examination of bond	periodically	2
Examination of timbe	8 r	3
	all species to be cut	3
	application to follow terms of contract	4
	area, cuttingbefore disposal under administrative use	3
	before disposal under administrative use	6
	camps and improvements	4
	claims, payment for timber cut from	3
	unperfected	3
	dead timberdiameter limits, approximate	
	estimate	
	by separate types	
	intensity of	
	of grades of material	4
	timber to be left	4
	explanation and demonstration to applicants	4
	field data submitted as map, estimate and report	4
	fire, precautions against	4
	Forest description.	4:
	future stand to be considered	3
	local needs, provision for	3
	logging and milling cost	4
	logging methods	
	map maximum annual cut considered before	
	method of cutting	
	mining locations, infested timber on	3
	timber on	
	unmarked	
	monopoly	
	nomenclature	
•	on Forests with preliminary plan	3
	working plan	
	period allowed for cutting	4
	protection from stock	3
	reliability and financial standing of applicants	4
	school and railroad sectionssize of sales	
	special clauses for applications.	4
	special clauses for insect-infested timber	4
	stumpage prices.	3
	utilization	40
Experiments, use of t	timber for	
Exportation of timber	r	
Extension of time ex	ceeding five years	3

·	Page.
Extension of time, form	33
when granted	32
when refused—disposal of timber	33
Farmers, free use to, in Alaska. Federal Government, other branches of, free use to. Fire menace, removal of timber under administrative use	12
Federal Government, other branches of, free use to	11
Fire menace, removal of timber under administrative use	62
Fishermen, free use to, in Alaska	12
rorest description, ranger's sales.	15
report on proposed sales	42 16
supervisor's unadvertised sales	10
Form A. Voucher	28
Form A. Voucher	22
59. Preliminary water-power permit	66
61. Water-power stipulation.	66
63 Transmission line permit	66
80. Railroad stipulations	66
80. Railroad stipulations	66
202. Timber sale application and agreement 17, 19, 23, 24, 33, 43,	70, 73
319. Memorandum of corporate officer's authority to sign instrument	24, 79
377. Bond 17, 25, 578a. Forest description 42, 62, 25, 26,	33, 77
578a. Forest description	65, 66
578b. Estimate sheet	65, 66
615. Timber sale record card	
616. Timber sale summary card.	60
820. Report of timber cut. 15, 832. Special use permit. 15,	99, OU
861. Letter of transmittal	17
874–8. Free use permit	
935. Certificate of publication	18 19
941. Bid for advertised timber	19 72
949. Supervisor's monthly report of timber cut and sold	60
975. Poster notice of sale of timber	23
Administrative use permit	63
Application for advance cutting. Application for cancellation of contract.	26
Application for cancellation of contract	34
Application for modification of contract	30
Application for modification of contract. Application for postponement brush piling Consent of surety.	33
Consent of surety.	31, 33
Extension of time	33
Notice of sale	21
Resolution	24 61
Timber sale costs. Transfer of credits.	29
Free use	
administration	69
amount allowed each applicant	ĭĭ
areas	$\overline{12}$
areas	11
cutting reports disposal of timber by, under administrative use regulation	70
disposal of timber by, under administrative use regulation	62
district forester's permits	70
limitation of cut under	
marking the timber	69
object of	67
permit areas	69
form	80
ranger's recordsranger's reports	70 70
regulations	11
restrictions	12 68
sale of material prohibited	12,00
scaling	69
schedule of rates	68
Secretary's and Forester's permits	70
special conditions in Alaska	12
sû pervisor's permits	70

Free use, temporary free-use areas.	70
to whom granted	11, 67
to whom refusedtransients and emergency use	
valuation of material	68
without permit	12
without permit. Fungus-infected timber, brush from, disposal of.	49
Future stand to be considered before making sale	37
General notice sales. Ground burning. See Brush disposal.	22
Ground burning. See Brush disposal. Ground rot	54
Heart rot.	5 4
Improvements. See also Camps and improvements.	00
exchange of timber for services, etc., in building, prohibited.	62
use of timber in making	
Insect-infested timber, disposal of brush from	49
disposal of, under administrative use	62
on mining locations.	38
special clauses for, in contracts	44 8
Installment payments. Letters of transmittal, general	30
rangers' sales	15
supervisor's advertised sales	17
Limitation of annual cut	7,13
basis for determining	13
district office procedure	14
supervisor to recommend	13
to be considered before examination of timber	36
under free use	13, 07
Local supply, future, no sale to endanger	38
Locations. See Mining locations.	•
Locomotives, steam, use of on National Forests	10
Logging costs, data on, in proposed sales	42
Logging methods, to be considered in examination of timber	37
Log lengths. See Scaling.	
Logs. See Scaling.	41
Map, proposed sale, preparation of	41 15
ranger's sale supervisor's unadvertised sale	16
Marking	9, 45
by supervisors	46
care to be exercised in determining method	47
check	48
clean cutting	48
demonstration to purchaserdiameter limits	46 47
district marking board	46
experienced men for.	46
free use timber	69
instructions, general	46
mature and defective trees	47
methods	45
policy, generalseed trees, when left	47
timber on claims.	48
trees to be left with crowns free.	47
witness and line trees.	48
Marking ax	9
Marking board, district	46
Maximum and minimum prices	
basis for determiningdistrict office procedure	14 14
supervisors to recommend	14
Maximum cut. See Limitation of annual cut.	1-1
Measuring. See Scaling.	
M1	52
35'11'	
Milling costs, data on, in proposed sales.	42

	Page.
Miners, free use to 11,	12, 67
Minimum and maximum prices	
Mining locations, insect-infested timber on	38
timber on	38
unmarked	39 58
Miscellaneous products, sale of	60
Mistakes, correction of, in advertisement	21
Modification of contracts. See Contracts.	
Monopoly, prevention of	9
Monopoly, prevention ofsale apportioned to prevent	38
Nomenclature	42
Notice of appeal, time within which it may be filed	10, 59
Notice of sale. See Advertisement.	50
Numbering logs	50 11 19
Organizations, cooperative, of settlers, free use to	11, 12
installment	8
must be made in advance of cutting	8, 27
postponement of, not allowed	30
under timber settlement	11,65
for timber on claims	39, 65
Permanent improvements. See Improvements.	
Permits, card record of administrative use, in supervisor's office	62
district forester's free use	70
duration of free use	68 62
form for administrative use	63
rangers record of administrative use	64
Secretary's and Forester's free use	70
supervisor's administrative use	62
supervisor's free use	70
Piling brush. See Brush disposal.	
Pin dote	54
Postponement brush piling. See Brush disposal.	00
Preliminary plans, proposed sales to be checked with	36
Private sale	14, 39
Procedure, advance cutting	26
district forester's sales	18
Forester's sales	20
ranger's sales, in supervisor's office	15
supervisor's advertised sales, in district office	18
supervisor's unadvertised sales	16
timber settlement, on Forests	65
Prospectors, free use to	12, 67
Publicity in large sales.	23
Publicity in large salesPunky sap	55
Railroad lands	39
Rangers sales. See Timber sales.	
Rates, schedule of, for free use material	68
Ravages, disposal of timber to prevent	10
Records and reports. See also Cutting reports.	
administrative use record, supervisor'srangers	62 64
annual report	60
appeals, record of	59
converting factors, use of, in preparing reports	60
cost data	61
form for reporting	61
cutting reports	59
district forester's and Forester's sales, supervisor's record	
of	18
district forester's monthly report.	60 18
district forester's record supervisor's sales	60
miscellaneous products, safe of, how reported	94

Records and reports	rangers free use record	70
tecords and reports,	reports	70
	ranger's sales record	15
	reports of timber cut under administrative use	64
	timber settlement	66
	scale record, supervisor's office	60
	anala rannets	59
	scale reportssummary timber sale record	60
	supervisor's advertised sales record	16
	timber cut and sold, report of	60
Refunds	some cut and sold, report of	
Removel period allo	wwad for	36 40
"Pomoved" defined	wed for	36
Perceted sales uned	lvertised timber prohibited	16
Repeated sales unad	a reports and Decords and reports	10
	g reports, and Records and reports.	94
Resolution, form of C	corporate	19 69
Restrictions under ir	ree user cut, damaged, killed, etc., on	12,08
Right of way, timber	r cut, damaged, killed, etc., on	10
Road districts, free u	180 to	11, 12
Roads, use of timber	in construction of, on National Forests	10
Rot, dote appearing	in knots	55
ground or stum	P	54
uniform center	or circular	53
	inistration of sales and Timber sales.	
miscellaneou	s forest products	58
Sample contracts in	district forester's and Forester's sales	18, 20
Sap, blue	and	55
punky or unsou	nd	55
Scale reports. See P	Records and reports, and Timber sales.	
Scale rule. See also	Scribner Decimal "C" log rule.	
special i	for Alaska and west slope of Cascades	51
Scaling	••••••••••••••••••••••••••••••••••••••	50
check on total	al number of logs	50
	•••••••••••	58
factors consid	lered	51
INC OUTS COILSIC	blue sap	55
	cat face	54
	circular shake	54
		56
	crotches	55
	curve and sweep	
	deep checks or seams	55
	deep spiral checks	55
	defects in logs	52
	defects in side of log	54
	dote appearing in knots	55
	finding diameters	52
	ground or stump rot	54
	measuring log lengths	52
	merchantable material	52
	pin dote	54
	punky or unsound sap	55
	uniform center or circular rot	53
	unnecessary loss in manufacture not considered	52
free use mate	erial	69
	······································	58
log lengths		50
mill scale stu	udies	58
numbering l	ogs	50
poles, posts.	etc	58
prohibition a	etcagainst removal before	9, 50
requirement	s of purchasers	50
scale rule	~ ~ £ ~ · · · · · · · · · · · · · · · ·	9,50
Scribner De	cimal "C" log rule tables.	56
shakes and a	hingle holts	58
gnacial mile	hingle bolts	51
atamaina los	A THE PARTY AND STATE OF ABCORDED	50
posmbing 108	sterial other than saw timber.	58
ша		•

	Page	٠.
Scaling tables, division of long logs		1
loss due to defent		
loss due to defect		
ties		8
Scattering brush. See Brush disposal.		
School districts, free use to		2
of 1 111.		
School lands Scribner Decimal "C" log rule, all timber to be sca		
Scribner Decimal "C" log rule, all timber to be sca	aled by 9, 50	0
tables		
Sooms doon		
Seams, deepSeedlings, wild, sale of	50	
how reported	60	0
Seed trees, where left	4'	7
Cained meterial cale of	2'	
Seized material, sale of	 4	•
Settlement. See Timber settlement.		
Settlers, cooperative organizations of, free use to		2
free use to	11 19 6	7
an 1 • 1	11, 12, 0	
Shake, circular	<u></u> <u>5</u>	
Size of sale, basis for determining		8
Skidding logs for scaling	50	n
Cound motorial defined		
Sound material, defined		
Spark arresters, when required		
Special use, timber cut, damaged, etc., in connecti	ion with 10	0
Special uses connected with sales	3	
Spiral checks, deep	5	
Stamping, by Forest officer only	•••••	9
logs after scaling		0
timber before removal		9
Stand, future, to be considered before making sale	3'	
Standard rates, schedule of, for free use material		8
Steam engines or locomotives, use of, on National	Forests 10	n
Steels protection from after outting completed	3'	
Stock, protection from, after cutting completed	······	•
Stone. See Free use.		
Stump rot	5	4
Stumpage prices	7 14 3	g
Supervision. See also Administration of free use as	nd calca	•
Supervision. See also Administration of free use at	na saies.	_
cutting under administrative use	6	3
Supervisor's sales. See Timber sales.		
Sureties. See also Bonds.		
burenes. See and Donus.	0.	_
consent of, to modifications	3	
form	31,33	3
Sweep or curve		
Tables, division of long logs		
The state of the s		
loss due to defect	E	6
loss due to defectScribner Decimal "C" log rule		
loss due to defectScribner Decimal "C" log rule	7 19	
loss due to defect. Scribner Decimal "C" log rule Timber sales	7, 13	
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting.	7, 13 8, 2	5
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of.	7, 1: 	5 3
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals.	7, 1: 8, 2½: 7, 1: 10, 5:	5 3 9
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals.	7, 1: 8, 2½: 7, 1: 10, 5:	5 3 9
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber.	7, 1 8, 2 7, 1 10, 5 7, 3	5 3 9
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make.	7, 1 8, 2 7, 1 10, 5 7, 3	5 3 9 7
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds.	7, 1 8, 2 7, 1 10, 5 7, 3	5 3 9 7 4
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds.	7, 1 8, 2 7, 1 10, 5 7, 3	5 3 9 7 4
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales.	7, 1: 8, 2: 7, 1: 10, 5: 7, 3: 10, 2: 10, 2:	5399744 4
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisemen	7, 1 8, 2 7, 1: 10, 5 7, 3 10, 2	539974444
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount.	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 1, 2	539974444
loss due to defect	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 1, 2	5399744449
loss due to defect	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 1, 2	5399744449
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount. conditions of sale. deposits.	7, 1 8, 2 7, 1: 10, 5: 7, 3: 10, 2 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.	53997444498
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount. conditions of sale. deposits. disposal by sale, under administrative	7, 1 8, 2 7, 1: 10, 5: 7, 3: 10, 2 1. 1. 1. 1. 2. 2. 3. 4. 5. 6. 8, 2. 9. 9. 9. 9. 9. 9. 9. 9. 9. 9	539974444982
loss due to defect	7, 1 8, 2 7, 1: 10, 5 7, 3 10, 2 11, 2 11, 1 11, 1 11, 1 11, 1 12, 2 13, 2 14, 1 15, 2 16, 2 17, 17, 1	5399744449828
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's.	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 1, tt 1 1, tt 1 1, tt 1 1, tt 1 1, tt 1, 1 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1	53997444498289
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisemen by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. advan	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 11 11 12 12 13 14 15 16 17 17 18 18 19 19 19 19 19 19 19 19 19 19 19 19 19	539974444982899
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisemen by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. advan	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 11 11 12 12 13 14 15 16 17 17 18 18 19 19 19 19 19 19 19 19 19 19 19 19 19	539974444982899
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisemen by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. advan	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 1. 1. 1. 1. 1. 2. 2. use regulation 6. 3, 2 4. use regulation 7, 1 1. nce cutting 1 1. ttisement, report of 1 18, 2	5399744449828990
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. advantagelication and sales. advantagelication advertisement by amount.	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 11, 2 11, 2 11, 3 11,	53997444498289908
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. advantadver applice. bids a	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 11, 2 11, 3 11, 2 11, 3 11,	539974444982899089
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisemen by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. sidvan adver applice bids a bond.	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 11, 2 11, 3 11, 2 11, 3 11,	539974444982899089
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisemen by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. sidvan adver applice bids a bond.	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 11, 2 11, 3 11, 2 11, 3 11,	5399744449828990899
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. sidvan advan advar applice bids a bond. card resident conditions of sales.	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.	53997444498289908998
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. sidvan advan advar applice bids a bond. card resident conditions of sales.	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 11, 2 11, 2 11, 3 11,	539974444982899089989
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. sidvan advan advar applice bids a bond. card resident conditions of sales.	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 11, 2 11, 2 11, 3 11,	539974444982899089989
loss due to defect. Scribner Decimal "C" log rule. Timber sales. advance cutting. annual cut, limitation of. appeals. appraisal of timber. authority to make. bonds. classification of sales. by advertisement by amount. conditions of sale. deposits. disposal by sale, under administrative district forester's and Forester's. sidvan advan advar applice bids a bond. card resident conditions of sales.	7, 1 8, 2 7, 1 10, 5 7, 3 10, 2 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.	539974444982899089989

Timber sales, district forester's and Forester's notice of salework which may be required of	18
supervisors	20
exportation of timber	•
installment payments. modifications of contracts.	0 96
payments	8, 3 (
prevention of monopoly	9, 38
prices, maximum and minimum	
private sale9,	14. 27
rangers	1
closing	18
contract	18
cutting reports	18
maps and forest description	18
modification of contract	18
procedure supervisor's office	18
refunds	23, 28
supervisor's advertised	16
advance cutting	17
application	16
bids and awardsbonds	17 17
closing	17
contracts.	17
district forester's record	ī
letter of transmittal	ī
notice of sale	16
procedure district office	18
report of advertisement	17
supervisor's unadvertised	16
maps and forest description	16
may not exceed \$100	16
procedurehititad	16
repeated sales prohibited	16 26 40
use of steam engines or locomotives	30, TO
Timber settlement	10, 6 8
closing	66
cutting reports	66
defined	68
deposits	66
how reported	66
payment on basis of estimate or scale	65
for timber on claims.	65
procedure on Forest	65
regulationspecial clauses in forms or stipulations	10 66
utilization	66
when referred to district forester	66
Time limits for cutting and removal under sales	36. 40
Trails, use of timber in construction of, on National Forests	10
Transfer of deposits	29
Transients, free use by	12, 68
Trespassers, free use to	11
award of sales to	
Turpentine, sale of	58
how reported	60
Unadvertised sales. See Timber sales.	
Unsound sap	55 88 71
Utilization	
Witnesses to execution of contract, etc	30 24
Witness trees. See Marking.	20.
Working plans, proposed sales to be checked with	36
₩ #	





